

STP 2626(1) – BENNINGTON

TABLE OF DRIVEWAYS			
STATION	POSITION	QUANTITY (SY)	TYPE OF HANDWORK
BENNINGTON VT. ROUTE 67A:			
1+55	LT	12	ASPHALT DRIVE
2+25	RT	30	ASPHALT DRIVE
3+85	LT	4	ASPHALT DRIVE
8+35	RT	13	ASPHALT DRIVE
39+30	RT	14	ASPHALT DRIVE
42+60	LT	16	ASPHALT DRIVE
42+70	RT	19	ASPHALT DRIVE
46+65	RT	4	ASPHALT DRIVE
48+10	RT	4	ASPHALT DRIVE
48+20	LT	4	ASPHALT DRIVE
49+15	RT	4	ASPHALT DRIVE
50+35	RT	4	GRAVEL DRIVE
52+30	RT	4	GRAVEL DRIVE
54+85	RT	4	GRAVEL DRIVE
56+70	RT	20	ASPHALT DRIVE
63+05	LT	4	GRAVEL DRIVE
64+85	LT	4	ASPHALT DRIVE
69+70	RT	4	ASPHALT DRIVE
70+80	RT	4	ASPHALT DRIVE
71+15	RT	4	ASPHALT DRIVE
71+20	LT	4	ASPHALT DRIVE
72+15	LT	4	ASPHALT DRIVE
72+70	RT	4	GRAVEL DRIVE
73+67	LT	60	ASPHALT DRIVE
75+05	RT	4	ASPHALT DRIVE
76+25	LT	7	GRAVEL DRIVE
80+80	RT	4	GRAVEL DRIVE
82+00	RT	16	GRAVEL DRIVE
82+80	RT	19	GRAVEL DRIVE
83+80	LT	21	GRAVEL DRIVE
84+15	RT	4	ASPHALT DRIVE
84+70	LT	4	ASPHALT DRIVE
85+80	RT	7	ASPHALT DRIVE
86+00	LT	4	GRAVEL DRIVE
86+60	RT	4	ASPHALT DRIVE
88+10	RT	4	GRAVEL DRIVE
89+95	RT	29	ASPHALT DRIVE
90+95	RT	4	ASPHALT DRIVE
91+45	LT	4	GRAVEL DRIVE
92+35	RT	4	GRAVEL DRIVE
93+10	RT	16	GRAVEL DRIVE
102+90	RT	4	ASPHALT DRIVE
105+30	RT	4	GRAVEL DRIVE
105+85	RT	4	ASPHALT DRIVE
107+00	LT	4	GRAVEL DRIVE
108+10	RT	4	ASPHALT DRIVE
108+75	LT	4	ASPHALT DRIVE
109+25	RT	13	ASPHALT DRIVE
109+80	LT	4	ASPHALT DRIVE
110+10	LT	4	ASPHALT DRIVE
110+30	LT	4	ASPHALT DRIVE
SUBTOTAL :		452	
ROUNDING :		23	
TOTAL :		475	

**STP 2622(I) – BENNINGTON
(NORTH BENNINGTON)**

TABLE OF DRIVEWAYS			
STATION	POSITION	QUANTITY (SY)	TYPE OF HANDWORK
NORTH BENNINGTON VT. ROUTE 67:			
12+35	LT	16	ASPHALT DRIVE
14+71	RT	20	GRAVEL DRIVE
15+04	LT	6	GRAVEL DRIVE
15+50	LT	6	GRAVEL DRIVE
15+76	LT	6	ASPHALT DRIVE
17+30	LT	6	GRAVEL DRIVE
18+30	RT	4	ASPHALT DRIVE
18+32	LT	6	ASPHALT DRIVE
18+63	RT	7	ASPHALT DRIVE
20+15	LT	11	ASPHALT DRIVE
21+15	LT	19	ASPHALT DRIVE
21+40	RT	4	ASPHALT DRIVE
22+25	RT	29	ASPHALT DRIVE
23+35	RT	9	ASPHALT DRIVE
24+30	RT	7	ASPHALT DRIVE
24+50	LT	12	ASPHALT DRIVE
24+80	LT	7	ASPHALT DRIVE
25+80	LT	8	ASPHALT DRIVE
26+45	LT	13	ASPHALT DRIVE
26+55	RT	8	ASPHALT DRIVE
26+90	LT	5	ASPHALT DRIVE
27+30	RT	8	ASPHALT DRIVE
27+45	LT	5	ASPHALT DRIVE
28+27	LT	6	ASPHALT DRIVE
28+35	RT	10	ASPHALT DRIVE
28+60	RT	9	ASPHALT DRIVE
28+90	LT	9	ASPHALT DRIVE
29+55	RT	15	ASPHALT DRIVE
29+95	LT	26	ASPHALT DRIVE
31+20	RT	16	GRAVEL DRIVE
32+65	RT	19	GRAVEL DRIVE
32+70	LT	15	GRAVEL DRIVE
34+05	LT	7	GRAVEL DRIVE
34+95	LT	7	GRAVEL DRIVE
SUBTOTAL:		361	
ROUNDING:		14	
TOTAL:		375	

**COMPOSITE
DRIVEWAY
HANDWORK
TABLES
SHEET**

PROJECT NAME: BENNINGTON & BENNINGTON (NORTH BENNINGTON) CLASS 1
 PROJECT NUMBER: STP 2626(I) & STP 2622(I)
 FILE NAME: p06b220.dgn PLOT DATE: 07-MAY-2012 14:2
 PROJECT LEADER: D.E.G. DRAWN BY: C.A.K.
 DESIGNED BY: M.J.L. CHECKED BY: D.E.G.
 DWG. NO. p06b220cdht.i SHEET 7 OF 69