QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

NON-PARTICIPATING	BRIDGE	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
			10	10	CY	COMMON EXCAVATION	203.15	EST.
			1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
			58,000	58,000	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	582
			80	80	TON	SUBBASE, RAP	301.40	EST.
			240	240	CWT	EMULSIFIED ASPHALT	404.65	11
			1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	
			6600	6600	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	286
			1	1	LU	AIR VOIDS PAY ADJUSTMEMT (N.A.B.I.)	490.31	
			1	1	LU	MAT DENSITY PAY ADJUSTMEMT (N.A.B.I.)	490.32	
			1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	
			1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	
	135			135	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3
	50			50	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST.
			12	12	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	
			11	11	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	
			11	11	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	
19				19	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	
			175	175	HR	POWER GRADER RENTAL	608.15	EST.
			50	50	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
			125	125	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
			300	300	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
			150	150	HR	TRUCK RENTAL	608.37	EST.
			125	125	HR	LOADER RENTAL, TYPE I	608.40	EST.
			2	2	CY	STONE FILL, TYPE I	613.10	EST.
			30	30	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	2
			10	10	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	1.6
			20	20	SF	DETECTABLE WARNING SURFACE	618.30	
			25	25	EA	YIELDING MARKER POSTS	619.17	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
52,375	SY	MAINLINE
5043	SY	SIDEROADS
582	SY	ROUNDING
58,000	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
4576	TON	WEARING COURSE (TYPE IVS)
1520	TON	LEVELING COURSE (TYPE IVS)
441	TON	SIDEROADS
22	TON	PULLOUTS
41	TON	ROUNDING
6600	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: BENNINGTON

PROJECT NUMBER: STP 2626(I)

FILE NAME: p06b220.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
DWG. NO. p06b220quan1.i

PLOT DATE: 07-MAY-2012 14:2
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 14 OF 69