STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS (SHS = FHWA STANDARD SIGNS BOOK)	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
BENNINGTON: VT. ROUTE 67A 6+95.0, RT	ONLY	1	30	30	6.25						1					X	~~X~~	X															SIGN ID CODE VR-921		E-145A
	SPEED LIMIT 40	1	24	30	5.00																												SIGN ID CODE R2-1		SHS
7+93.0, C/L		1 1	24 24	30 24	5.00 4.00						1					X		X															BACK-TO-BACK SIGN ID CODE R4-7 SIGN ID CODE R3-4		SHS SHS
		1 1	18 18	18 18	2.25 2.25																												BACK-TO-BACK SIGN ID CODE OMI-1 SIGN ID CODE OMI-1		E-150 E-150
8+14.0, LT	TO MORSE RD PERCEY RD						1 1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0671 0202 0160	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		SHS E-138
8+81.0, LT	LEGAL LOAD AS FOR STATE HIGHWAYS	1	24	30	5.00						1					X		X															SIGN ID CODE VR-079		E-141
8+94.0, C/L		1	24	30	5.00						1					X		X															SIGN ID CODE R4-7		SHS
		1 1	18 18	18 18	2.25 2.25																												BACK-TO-BACK SIGN ID CODE OMI-1 SIGN ID CODE OMI-1		E-150 E-150
14+77.0, RT	ONLY ONLY	1	60	30	12.50						2					X		X															SIGN ID CODE VR-941		E-145A
TOTALS		SF 58.42	SF	EA. 2	SF							LF	LF	LF	LF	LF 84	LF 14		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: BENNINGTON
PROJECT NUMBER: STP 2626(I)

FILE NAME: p06b220.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
DWG. NO. p06b220tss2.i

PLOT DATE: 07-MAY-2012 14:2
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 42 OF 69