QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	20	20	CY	COMMON EXCAVATION	203.15	4.6
	1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
	10,450	10,450	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	73
	20	20	TON	SUBBASE, RAP	301.40	2.9
	45	45	CWT	EMULSIFIED ASPHALT	404.65	3
	1	1	LU	PRICE ADJUSTMENT ASPHALT CEMENT (N.A.B.I.)	406.50	EST.
	1250	1250	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	50
	1	1	LU	AIR VOIDS PAY ADJUSTMEMT (N.A.B.I.)	490.31	EST.
	1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	
	1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	
	1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	
	12	12	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	
	50	50	HR	POWER GRADER RENTAL	608.15	EST.
	20	20	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
	20	20	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
	30	30	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
	30	30	HR	TRUCK RENTAL	608.37	EST.
	30	30	HR	LOADER RENTAL, TYPE I	608.40	EST.
	60	60	LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	4
	55	55	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	3.1
	100	100	SF	DETECTABLE WARNING SURFACE	618.30	
	5	5	EA	YIELDING MARKER POSTS	619.17	EST.
	9	9	EA	ADJUST ELEVATION OF VALVE BOX	629.20	
	350	350	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.
	500	500	HR	FLAGGERS	630.15	EST.
	40	40	HR	FLAGGERS, RAILROAD	630.20	EST.
0.5		0.5	LS	TESTING EQUIPMENT, CONCRETE	631.16	EST.
0.5		0.5	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	EST.
	0.5	0.5	LS	MOBILIZATION/DEMOBILIZATION	635.11	
	1	1	LS	TRAFFIC CONTROL (STP 2622(I))	641.10	EST.
	0.5	0.5	LS	PUBLIC RELATIONS OFFICER	641.12	
	3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
9807	SY	MAINLINE
570	SY	SIDEROADS
73	SY	ROUNDING
10,450	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
858	TON	WEARING COURSE (TYPE IVS)
286	TON	LEVELING COURSE (TYPE IVS)
48	TON	SIDE ROADS
58	TON	ROUNDING
1250	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: BENNINGTON (NORTH BENNINGTON) CLASS I

PROJECT NUMBER: STP 2622(I)

FILE NAME: p06b212.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
DWG. NO. p06b212quan1.i

PLOT DATE: 07-MAY-2012 14:2
DRAWN BY: C.A.K.
CHECKED BY: R.A.B.
SHEET 53 OF 69