STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
NORTH BENNINGTON: 25+72.0, LT	R	1	24	24	4.00						1					X		X															SIGN ID CODE R8-3A		SHS
26+66.0, RT	SPEED LIMIT 25	1	24	30	5.00						1					X		X															SIGN ID CODE R2-1		SHS
27+90.0, RT	RR	1	36	36	7.10						2					X		X															SIGN ID CODE W10-1		SHS
29+40.0, LT	R	1	24	24	4.00						1					X		X															SIGN ID CODE R8-3A		SHS
	BEGIN	1	24	12	2.00																												SIGN ID CODE M4-11		
29+62.0, RT	MAIN ST						1				1					X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	DEPOT ST						1																										SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 0670 0202 0056	1 1	30 6	30 10	6.25 0.42																												BACK-TO-BACK SIGN ID CODE R1-1 SIGN ID CODE VD-700		SHS E-138
29+70.0, RT		1	30	30	6.25						1					X		X															SIGN ID CODE W11-2 SIGN SHALL BE FLUORESCENT-YELLOW GREEN.		SHS
		1	24	12	2.00																												SIGN ID CODE W16-7p SIGN SHALL BE FLUORESCENT-YELLOW GREEN.		SHS
	TOTALS				SF 37.02	SF	EA. 2	SF				LF	LF	LF	LF	LF 98	LF		EA.	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #4

PROJECT NAME: BENNINGTON (NORTH BENNINGTON) CLASS 1

PROJECT NUMBER: STP 2622(1)

FILE NAME: p06b212.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
DWG. NO. p06b212tss4.i

PLOT DATE: 07-MAY-2012 14:2
DRAWN BY: C.A.K.
CHECKED BY: R.A.B.
SHEET 66 OF 69