STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																							
6+86 RT	NORTH	1	24	12	2.00						1					15		X															M3-1		E-135
	91	1	24	24	4.00																												M1-1		E-135
	←	1	21	15	2.19																												M6-1		E-135
7+59 LT	NORTH	1	24	12	2.00				X																								M3-1 RETAIN POSTS, FRAME AND FIVE EXISTING SIGNS ON THIS ASSEMBLY		E-135
10+02 RT	BRIDGE 1 VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
10+56 RT	1030 1314 0020	1	6	10	0.42						1				15.0			X																	E-138
11+13 LT	BRIDGE 1 VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
11+16 LT	↑ BELLOWS FALLS 3	1	72	12	6.00						2					30.0		X															D1-1		E-123
	← SPRINGFIELD 11	1	72	12	6.00																												D1-1		E-123
	← WHITE RIVER JCT 37	1	72	12	6.00																												D1-1		E-123
11+82 LT		1	36	36	9.00						2					30.0		X															W4-2		E-151
13+87 LT	ONE WAY	1	36	12	3.00				X																								R6-1L INSTALL ON "DO NOT ENTER" SIGN		E-142
14+08 LT	ONE WAY / ONE WAY	1 1	36 36	12 12	3.00 3.00				X																								R6-1R R6-1L INSTALL ON THE EXISTING POST WITH "DO NOT ENTER" SIGN BACK TO BACK		E-142
SHEET TOTALS					SF 47.27	SF	EA.	EA.				FT			FT 45.0	FT 75.0	FT		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB				
															FT 120.0																				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(1)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tss02.i

PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 63 OF 82