STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
14+51 LT		1	30	30	6.25						1					15.0		X																W4-1		E-150
16+35 RT	ROCKINGHAM 3	1	72	12	6.00						2					30.0		X																DI-1		E-123
	RUTLAND 46	1	72	12	6.00																													DI-1		E-123
	BRATTLEBORO 28	1	72	12	6.00																													DI-1		E-123
16+67 RT	BRIDGE 1A VT 103	1	6	8	0.33						1				15.0			X																VD-701		E-134
16+78 LT	BRIDGE 1A VT 103	1	6	8	0.33						1				15.0			X																VD-701		E-134
20+47 LT	SOUTH						1				1					15.0		X																M3-3		E-135
							1																											MI-1		E-135
							1																											M6-1		E-135
21+12 LT	1030 1314 0040	1	6	10	0.42						1				15.0			X																		E-138
22+00 LT	SOUTH						1				1					15.0		X																M3-3		E-135
							1																											MI-1		E-135
							1																											M6-2		E-135
SHEET TOTALS		SF 25.33	SF	EA. 6	EA.		FT	FT	FT	FT 45.0	FT 75.0	FT 120.0	EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB										

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #3

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(I)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tss03.i

PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 64 OF 82