STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #5

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.16	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
36+69 LT	BRIDGE 18 VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
40+84 LT	STOP 1030 1314 0078	1 1	30 6	30 10	6.25 0.42						1					15.0		X															RI-1 BACK TO BACK		E-143 E-138
40+85 LT	OLD DARBY HILL RD TH 84						1				1					15.0		X																	
40+99 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15.0		X															VR-017		E-141
42+24 LT	1030 1314 0080	1	6	10	0.42						1				15.0			X																	E-138
52+80 RT	1030 1314 0100	1	6	10	0.42						1				15.0			X																	E-138
59+76 RT	SCHOOL BUS DEPOT RD TH 75 LEGAL LOAD LIMIT 24,000 POUNDS	 1	 24	 30	 5.00		1				1					15.0		X															SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF LEGAL LOAD LIMIT SIGN. VR-017		 E-141
60+24 RT	STOP 1030 1314 0114	1 1	30 6	30 10	6.25 0.42						1					15.0		X															RI-1 BACK TO BACK		E-143 E-138
63+30 RT	BRIDGE 1C VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
63+36 LT	1030 1314 0120	1	6	10	0.42						1				15.0			X																	E-138
63+72 LT	BRIDGE 1C VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
64+80 LT	SPEED LIMIT 50	1	24	30	5.00						1					15.0		X															R2-1		E-142
												FT	FT	FT	FT	FT	FT	EA	LB	LB	LB		LB	LB	LB	LB									
															90.0	90.0																			
SHEET TOTALS		SF 30.59	SF	EA. 2	EA.							FT			FT 180.0				LB	EA.		LB					EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #5

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(I)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tss05.i
PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 66 OF 82