STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
95+04 RT	1030 1314 0180	1	6	10	0.42						1				15.0			X																	E-138
101+97 LT	MEETING HOUSE TH 78 RD						1				1					15.0		X															RI-1		E-143
	STOP 1030 1314 0194	1	30	30	6.25																											BACK TO BACK		E-138
		1	6	10	0.42																													
102+51 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15.0		X															VR-017		E-141
103+25 RT	NORTH	1	24	12	2.00						1					15.0		X															M3-1		E-136B
	VERMONT 103	1	30	24	5.00																												M1-5		E-136B
105+25 RT	SPEED LIMIT 50	1	24	30	5.00						1					15.0		X															R2-1		E-142
105+60 LT	1030 1314 0200	1	6	10	0.42						1				15.0			X																	E-138
109+69 LT		1	30	30	6.25						1					15.0		X															W2-2M		E-155
	MEETING HOUSE RD	1	30	18	3.75																												W16-8	81	
116+16 RT	1030 1314 0220	1	6	10	0.42						1				15.0			X																	E-138
125+03 RT	BRIDGE 3 VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
125+03 LT	BRIDGE 3 VT 103	1	6	8	0.33						1				15.0			X															VD-701		E-134
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
															75.0	75.0																			
SHEET TOTALS		SF 35.59	SF	EA. 1	EA.							FT			FT 150.0					LB			EA.		LB			EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #7

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(I)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tss07.i

PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 68 OF 82