STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
125+94 LT	NARROWS TH 27 RD						1				1					15.0		X																SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1314 0239	1	30	30	6.25																											RI-1 BACK TO BACK		E-143
		1	6	10	0.42																													E-138
126+28 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15.0		X																VR-017		E-141
129+90 RT	WATCH FOR TURNING VEHICLES						1				2					30.0		X																		
	NEXT 1500 FT						1																													
130+84 RT	BRIDGE 4 VT 103	1	6	8	0.33						1				15.0			X																VD-701		E-134
137+28 RT	1030 1314 0260	1	6	10	0.42																												SIGN TO BE INSTALLED BELOW TRAVEL INFORMATION SIGNS.		E-138
147+84 LT	1030 1314 0280	1	6	10	0.42						1				15.0			X																		E-138
150+74 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15.0		X																VR-017		E-141
150+74 LT	WATCH FOR TURNING VEHICLES						1				2					30.0		X																		
	NEXT 1500 FT						1																													
151+09 RT	COUNTRY CLUB RD TH 77						1				1					15.0		X																SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1314 0286	1	30	30	6.25																											RI-1 BACK TO BACK		E-143
		1	6	10	0.42																													E-138
SHEET TOTALS		SF 24.51	SF	EA. 6	EA.							FT	FT	FT	FT 30.0	FT 120.0	FT		EA	LB	LB	LB	EA.	LB	LB	LB	LB	EA.	EA.	LB					
												FT			FT 150.0					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #8

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(I)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tss08.i
PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 69 OF 82