STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #13

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REMOVED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
263+78 RT	WILLIAMS RD TH 14						1				1					15.0		X																SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1314 0499	1	30	30	6.25																												R1-1 BACK TO BACK		E-143
		1	6	10	0.42																														E-138
264+85 RT	NORTH	1	24	12	2.00						1					15.0		X																M3-1		E-136B
	VERMONT 103	1	30	24	5.00																												MI-5		E-136B
268+00 ~~LT~~ RT	SPEED LIMIT 50	1	24	30	5.00						1					15.0		X																R2-1		E-142
274+55 RT	1030 1314 0520	1	6	10	0.42																												SIGN TO BE INSTALLED BELOW TRAVEL INFORMATION SIGN.		E-138
283+31 RT	LEGAL LOAD LIMIT 6,000 POUNDS	1	24	30	5.00						1					15.0		X																		E-141
284+09 RT	LOWER BARTONSVILLE TH 8						1				1					15.0		X																SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1314 0537	1	30	30	6.25																												R1-1 BACK TO BACK		E-143
		1	6	10	0.42																														E-138
285+12 LT	1030 1314 0540	1	6	10	0.42						1					15.0		X																		E-138
295+68 LT	1030 1314 0560	1	6	10	0.42						1					15.0		X																		E-138
301+14 RT	BRIDGE 6 VT 103	1	6	8	0.33						1					15.0		X																VD-701		E-134
301+66 LT	BRIDGE 6 VT 103	1	6	8	0.33						1					15.0		X																VD-701		E-134

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

						FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB			
									60.0	75.0														
SHEET TOTALS	SF 32.26	SF	EA. 2	EA.		FT			FT 135.0					LB			EA.	LB				EA.	EA.	LB

TRAFFIC SIGN SUMMARY SHEET #13

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(I)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tssI3.i

PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 74 OF 82