STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET #17

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																								
C 29+62 RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15.0		X															VR-017		E-141
C 30+00 RT	PECK RD TH 104						1				1					15.0		X															SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1407 0056	1	30	30	6.25																											RI-1 BACK TO BACK		E-143
		1	6	10	0.42																													E-138
C 31+68 RT	1030 1407 0060	1	6	10	0.42						1				15.0			X																E-138
C 33+33 LT	HORSESHOE RD TH 60						1				1					15.0		X															SIGN TO BE INSTALLED USING TOP MOUNTING BRACKET, MOUNTED 1.0' FROM AND PERPENDICULAR TO TOP OF STOP SIGN.		
	STOP 1030 1407 0064	1	30	30	6.25																											RI-1 BACK TO BACK		E-143
		1	6	10	0.42																													E-138
C 33+74 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15.0		X															VR-017		E-141
C 34+75 RT	NORTH	1	24	12	2.00						1					15.0		X															M3-1		E-136B
	VERMONT 103	1	30	24	5.00																											MI-5		E-136B
C 36+75 RT	SPEED LIMIT 50	1	24	30	5.00						1					15.0		X															R2-1		E-142
C 42+24 LT	1030 1407 0080	1	6	10	0.42						1				15.0			X																E-138
C 52+80 RT	1030 1407 0100	1	6	10	0.42						1				15.0			X																E-138
C 56+91 LT		1	30	30	6.25						1					15.0		X															WII-7		

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST "SIGN POST DESIGN GUIDELINE."

						FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB				
									45.0	105.0															
SHEET TOTALS	SF 42.85	SF	EA. 2	EA.		FT			FT 150.0					LB			EA.	LB				EA.	EA.	LB

TRAFFIC SIGN SUMMARY SHEET #17

PROJECT NAME: ROCKINGHAM-CHESTER
PROJECT NUMBER: NH 2628(I)

FILE NAME: 06B224
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: pb224tssl7.i

PLOT DATE: 31-AUG-2012 14:04
DRAWN BY: MRS
CHECKED BY: PTS
SHEET 78 OF 82