STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET

CURB

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	REMARKS
616.21 - VERTICAL GRANITE CURB				
38+86.67 RT	39+05.72 RT		19	
41+00.00 RT	42+11.87 RT		112	MEDIAN
WITH SLOPE TO VERTICAL TRANSITION SECTION				
41+00.00 RT	42+42.00 RT		142	MEDIAN
WITH SLOPE TO VERTICAL TRANSITION SECTION				
42+00.97 RT	42+12.20 RT		11	
42+12.37 RT	42+42.50 LT		46	MEDIAN
42+17.16 RT	42+22.34 RT		7	
42+17.37 RT	42+47.50 LT		46	MEDIAN
42+17.87 RT	42+36.63 RT		19	MEDIAN
42+35.50 LT	42+42.50 LT	7		
42+36.63 RT	42+68.37 RT		35	MEDIAN
				70'RAD
42+47.50 LT	42+54.50 LT	7		
42+48.00 RT	42+67.73 RT		20	MEDIAN
42+67.73 RT	42+68.37 RT		3	MEDIAN
				2' RAD
SUBTOTAL		14	460	474
ROUND				11
TOTAL				485
616.28 - CAST-IN-PLACE CONCRETE CURB, TYPE B				
39+16.28 RT	39+35.93 RT		20	DRIVE
SUBTOTAL			20	20
ROUND				5
TOTAL				25

SIDEWALK

BEGIN STATION	END STATION	POSITION LEFT SY	POSITION RIGHT SY	REMARKS
618.10 - PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH				
42+04.17 RT	42+08.24 RT		6.7	4' WIDTH
42+04.24 RT	42+12.17 RT		5.5	SLOPED PAD
42+12.12 RT	42+17.12 RT		4.5	RAMP
42+12.39 RT	42+47.50 LT		25.4	MEDIAN
42+37.39 LT	42+52.49 LT	10.5		RAMP
SUBTOTAL		10.5	42.1	52.6
ROUND				2.4
TOTAL				55.0

GUARD RAIL

BEGIN STATION	END STATION	POSITION LEFT FT	POSITION RIGHT FT	END TREATMENT BEGIN EA	END TREATMENT END EA

UNDERDRAIN

BEGIN STATION	END STATION	TYPE	POSITION	DIA. IN	LENGTH FT	TRENCH EARTH CY	TRENCH ROCK CY	GRAN BKFILL CY	FB EA	MKR PST EA

PROJECT NAME: COLCHESTER
PROJECT NUMBER: TCSP TCSE (9)

FILE NAME: t06b242frm.dgn
PROJECT LEADER: J. SCHULTZ
DESIGNED BY: D. LYMAN
ITEM DETAIL SHEET

PLOT DATE: 23-FEB-2012
DRAWN BY: D. LYMAN
CHECKED BY: J. SCHULTZ
SHEET 6 OF 22