STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 2

APPROXIMATE SUMMARY OF QUANTITIES

R.O.W.	EMPLOYEE TRAINEESHIP	FULL CE	GOV'T PARTICIPATING BRIDGE	GOV'T PARTICIPATING ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				300	300	LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21	18.7
				129	129	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	--
				3	3	EA	MANUFACTURED TERMINAL SECTION, TANGENT	621.51	--
				15	15	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	--
				30,500	30,500	LF	REMOVAL AND DISPOSAL OF GUARD RAIL	621.80	137.5
				42	42	EA	REMOVAL AND DISPOSAL OF GUIDE POSTS	621.81	--
				1,250	1,250	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
				4,000	4,000	HR	FLAGGERS	630.15	EST
		1			1	LS	FIELD OFFICE, ENGINEERS	631.10	--
		1			1	LS	TESTING EQUIPMENT, CONCRETE	631.16	--
		1			1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	--
		1			1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	EST
				1	1	LS	MOBILIZATION/DEMOBILIZATION	635.11	EST
				1	1	LS	TRAFFIC CONTROL	641.10	EST
				2	2	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	--
				133,000	133,000	LF	DURABLE 4IN WHITE LINE, THERMOPLASTIC	646.402	--
				124,200	124,200	LF	DURABLE 4IN YELLOW LINE, THERMOPLASTIC	646.412	--
				180	180	LF	DURABLE 24 IN STOP BAR, THERMOPLASTIC	646.482	--
				42	42	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	--
				266,000	266,000	LF	TEMPORARY 4IN WHITE LINE, PAINT	646.602	EST
				248,300	248,300	LF	TEMPORARY 4IN YELLOW LINE, PAINT	646.612	EST
				250	250	LF	TEMPORARY 24IN STOP BAR, PAINT	646.682	EST
				50	50	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	--
				2,000	2,000	EA	LINE STRIPING TARGETS	646.76	EST
				3,600	3,600	SY	GEOTEXTILE UNDER STONE FILL	649.31	160
				240	240	LB	SEED	651.15	EST
				2,000	2,000	LB	FERTILIZER	651.18	EST
				8	8	TON	AGRICULTURAL LIMESTONE	651.20	EST
				8	8	TON	HAY MULCH	651.25	EST
				50	50	CY	TOPSOIL	651.35	EST
				2,100	2,100	SY	TEMPORARY EROSION MATTING	653.20	11
				168	168	SF	TRAFFIC SIGNS, TYPE A	675.20	0.42
							- BEGIN OPTION ITEMS -		
				525	525	LF	FLANGED CHANNEL SIGN POSTS	675.301	EST
				525	525	LF	SQUARE TUBE STEEL POST AND ANCHORS	675.341	EST
							- END OPTION ITEMS -		
				42	42	EA	REMOVING SIGNS	675.50	--
				10	10	EA	ERECTING SALVAGED SIGNS	675.60	--
				154	154	EA	DELINEATOR WITH STEEL POST	676.10	EST
				215	215	LF	VEHICLE LOOP DETECTOR	678.22	EST
				1	1	EA	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	EST
			232		232	LF	SPECIAL PROV. (BRIDGE RAILING REPAIR, TYPE II)	900.640	0.75

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

STATIONS FROM	STATIONS TO	PAVEMENT WIDTHS			EQUATIONS +	EQUATIONS -	FEET	MILES	REMARKS

TOTALS

QUANTITY SHEET #2

PROJECT NAME **MAIDSTONE - BLOOMFIELD** 06c042.dgn/06c042qs2.l
PROJECT NUMBER **STP 2609(1)S**

DATE PLOTTED 24-AUG-2009