STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 1

KILOMETER MARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD. lb/ft 1.7	FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																									
MAIDSTONE 395+17 LT	STOP 1020 0515 0749	1	30	30	6.25		1				1			X		X																		BACK TO BACK		E-143
395+57 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1			X		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
395+57 LT	SPEED LIMIT 30						1				1			X		X																				
BRUNSWICK 116+25 LT	STOP	1	30	30	6.25						1			X		X																				E-143
117+10 LT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.0						1			X		X																		REFER TO STANDARD E-121 FOR PLACEMENT.		E-141
130+05 RT	NARROW BRIDGE	1	30	30	6.25						1			X		X																				E-154
136+57 LT		1	12	36	3.0						1			X		X																				E-120
136+65 RT		1	12	36	3.0						1			X		X																				E-120
	BRIDGE 6 VT 102	1	6	8	0.33																																E-134
137+71 LT		1	12	36	3.0						1			X		X																				E-120
	1020 0505 0260						1																													
	BRIDGE 6 VT 102						1																													
137+85 RT		1	12	36	3.0						1			X		X																				E-120
143+90 LT	NARROW BRIDGE	1	30	30	6.25						1			X		X																				E-154
			SF	SF	EA.	SF						LF	LF	LF 165	LF	LF 165	LF			EA.	LB	LB	LB		EA.	LB	LB	LB		EA.	EA.	LB					
	SHEET TOTALS		47.33		4							165				165																					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #1

PROJECT: **MAIDSTONE – BLOOMFIELD** | PROJECT NO.: **STP 2609(1)S** | DATE: 8-06

DESIGN FILE NAME: 06c042.dgn
IPARM FILE NAME: 06c042tsl.I
SURVEYED BY:
SQUAD LEADER:

PLOT DATE: 24-AUG-2009 08:4
SURVEY DATE:
DRAWN BY: C.E.A., INC.
SHEET: **35** OF **40**