LOCATION			CURB	GUARDRAIL																REMARKS
			616.35	621.20	621.205	621.21	621.50	621.51	621.60	621.76	621.77	621.79	621.80	621.81	900.620					
STATION	STATION	POS.	TREATED TIMBER CURB	STEEL BEAM GUARDRAIL GALV.	STEEL BEAM GUARDRAIL GALV. W/8' POSTS	HD STEEL BEAM GUARDRAIL GALV.	M.T.S. FLARED	M.T.S. TANGENT	ANCHOR FOR STEEL BEAM RAIL	REPLACE GUARDRAIL POST ASSEMBLY	REPLACE GUARDRAIL BEAM UNIT	ADJUST HEIGHT OF GUARDRAIL	REMOVAL & DISP. OF GUARDRAIL	REMOVAL & DISP. OF GUIDE POSTS	SPECIAL PROVISION (DELIN. W/ STEEL POST)					
			LF	LF	LF	LF	EACH	EACH	EACH	EACH	EACH	LF	LF	EACH	EACH					
BLOOMFIELD																				
28+96	366+94	LT/RT								120	60									
31+15.0	40+59.0	RT											944.0							
31+12.0	40+62.0	RT		875.0			2								2					MTS 31+12 TO 31+49.5, MTS 40+24.5 TO 40+62
60+23.0	60+60.5	RT					1						37.5		1					REMOVE MELT
60+60.5	69+51.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
69+51.5	69+89.0	RT					1						37.5		1					REMOVE MELT
70+18.0	70+55.5	RT					1						37.5		1					REMOVE MELT
70+55.5	81+99.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
81+99.5	82+37.0	RT					1						37.5		1					REMOVE MELT
83+01.0	83+38.5	RT					1						37.5		1					REMOVE MELT
83+38.5	85+10.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
85+10.5	85+48.0	RT					1						37.5		1					REMOVE MELT
84+78.0	85+15.5	LT											37.5							REMOVE MELT
84+28.0	85+15.5	LT		50.0			1								1					MTS 84+28 TO 84+65.5, CONNECT SBGR TO EXISTING GUARDRAIL
85+15.5	85+45.0	LT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
85+39.5	85+48.0	LT											25.0							
85+39.5	85+48.0	LT		27.0					1						1					8.5' RADIUS; ANCHOR @ 85+48; SEE STANDARD G-1D
86+20.0	86+57.5	RT					1						37.5		1					REMOVE MELT
86+57.5	92+36.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
92+36.5	92+74.0	RT					1						37.5		1					REMOVE MELT
96+17.0	96+54.5	RT					1						37.5		1					REMOVE MELT
96+54.5	106+52.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
106+52.5	106+90.0	RT					1						37.5		1					REMOVE MELT
111+55.0	111+92.5	RT					1						37.5		1					REMOVE MELT
111+92.5	114+51.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
114+51.5	114+89.0	RT					1						37.5		1					REMOVE MELT
127+71.0	128+33.5	RT											62.5							REMOVE MELT AND DAMAGED GUARDRAIL
127+71.0	128+33.5	RT		25.0			1								1					MTS 127+71 TO 128+08.5
128+33.5	129+56.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
129+56.5	129+94.0	RT					1						37.5		1					REMOVE MELT
129+32.0	129+39.5	LT											37.5							
129+32.0	129+39.5	LT		39.5					1											8.5' RADIUS; ANCHOR @ 129+32; SEE STANDARD G-1D
129+38.0	130+64.5	LT													1					RETAIN EXISTING STEEL BEAM GUARDRAIL
130+64.5	131+02.0	LT					1						37.5		1					REMOVE MELT
154+78.0	155+15.5	RT					1						37.5		1					REMOVE MELT
155+15.5	158+02.0	RT													1					RETAIN EXISTING STEEL BEAM GUARDRAIL
157+76.0	158+13.5	LT					1						37.5		1					REMOVE MELT
158+13.5	163+18.5	LT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
163+18.5	163+56.0	LT					1						37.5		1					REMOVE MELT
158+47.0	158+84.5	RT					1						37.5		1					REMOVE MELT
158+84.5	165+08.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
165+08.5	165+46.0	RT					1						37.5		1					REMOVE MELT
171+77.0	172+14.5	RT					1						37.5		1					REMOVE MELT
172+14.5	173+27.5	RT																		RETAIN EXISTING STEEL BEAM GUARDRAIL
173+27.5	173+65.0	RT					1						37.5		1					REMOVE MELT
SUBTOTAL SHEET 11			0.0	1016.5	0.0	0.0	25	0	2	120	60	0.0	1894.0	0	28					

ITEM DETAIL SUMMARY SHEET 1

PROJECT NAME: BLOOMFIELD-LEMINGTON

PROJECT NUMBER: STP 2610(I)

FILE NAME: /pave/06c052/pc052
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: 06C052_II

PLOT DATE: 19-JUN-2013 16:59
DRAWN BY: SNG
CHECKED BY: PTS
SHEET II OF 82