COMPOSITE QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP SRIN(004)		NH HES 020-1(21)		STP HES 2614(1)S					STP 2615(1)S			SUMMARY OF ESTIMATED QUANTITIES				
FULL C.E.	ROADWAY	EPSC	FULL C.E.	ROADWAY	FULL C.E.	NON-PARTICIPATING	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	FULL C.E.	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
				3									3	EA	THINNING AND TRIMMING FOR SIGNS	201.31	
	20			840					15			40	915	CY	COMMON EXCAVATION	203.15	
									250				250	CY	UNCLASSIFIED EXCAVATION	203.17	
				555					250				805	CY	EARTH BORROW	203.30	
	20												20	CY	TRENCH EXCAVATION OF EARTH	204.20	
	1			1					1			1	4	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	
				40,800					104,000			37,725	182,525	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	
				4800									4800	LF	MILLED RUMBLE STRIPS	213.10	
	24			200					200			40	464	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	
									16			45	61	TON	SUBBASE, RAP	301.40	
				10					50				60	TON	AGGREGATE SHOULDERS	402.12	
				250					20				270	TON	AGGREGATE SHOULDERS, RAP	402.13	
				170					430			160	760	CWT	EMULSIFIED ASPHALT	404.65	
	1			1					1			1	4	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	
															BEGIN OPTION AA		
	2			4650					11,850			4375	20,877	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0.0% RAP CONTENT)	490.30	
	2			4650					11,850			4375	20,877	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0.0% < RAP CONTENT <15.0%)	490.30	
	2			4650					11,850			4375	20,877	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% <= RAP CONTENT < 25.0%)	490.30	
	2			4650					11,850			4375	20,877	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% <= RAP CONTENT <= 50.0%)	490.30	
															END OPTION AA		
				1					1			1	3	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	
								350			70		420	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	
								82					82	LF	REMOVAL OF EXISTING RAIL	525.10	
								100					100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	525.60	EST.
								82					82	LF	BRIDGE RAILING REPAIR, TYPE III	580.20	
															BEGIN OPTION BB		
	28												28	LF	18" CSP .064 (2 2/3" x 1/2")	601.0015	
	28												28	LF	18" CPEP (SL)	601.2615	
															END OPTION BB		

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIR HAVEN - CASTLETON & FAIR HAVEN
STP HES 2614(1)S, STP 2615(1)S,
PROJECT NUMBER: NH HES 020-1(21) & STP SRN (004)

FILE NAME: p06c058.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06c058cqsl.i

PLOT DATE: 22-FEB-2012 12:45
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 3 OF 157