



SIGN LEGEND

RWA = ROAD WORK AHEAD
RW500 = ROAD WORK 500 FEET
ERW = END ROAD WORK
RWN = ROAD WORK NEXT 6 MILES

◁ = PORTABLE CHANGEABLE MESSAGE SIGN (PCMS)

CONSTRUCTION APPROACH SIGNING

HES 020-(K2) FAIR HAVEN					
HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER
U.S. ROUTE 4 NY APPROACH	1	1	1		1-PCMS
U.S. ROUTE 4					1-PCMS
U.S. ROUTE 4 WESTBOUND	2		2		1-PCMS
U.S. ROUTE 4 EASTBOUND		2			
TOTAL	3	3	3		3-PCMS

STP 2615(I)S FAIR HAVEN CLASS I						
HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER	
CEDAR STREET (TH-55)	1	1				
GROVE STREET (TH-64)	1	1				
PLEASANT STREET (TH-57)	1	1				
ADAMS STREET (TH-50)	1	1				
VT. ROUTE 22A	2	1	2			1-PCMS
MARBLE STREET (TH-54)	1	1				
RIVER STREET (TH-8)	1	1				
LIBERTY STREET (TH-44)	1	1				
SOUTH PARK PLACE (TH-53)	1	1				
MAPLE STREET (TH-43)	1	1				
N. PARK PLACE FORK (TH-3)	1	1				
N. PARK PLACE (TH-3)	1	1				
ALLEN STREET (TH-41)	1	1				
TOTAL	14	13	2			1-PCMS

STP HES 2614(I)S FAIR HAVEN - CASTLETON					
HIGHWAY NAME	RWA	ERW	RW500	RWN	OTHER
SWAMP ROAD (TH-9)	1	1			
PINE STREET (TH-32)	1	1			
CREEK ROAD (TH-2)	1	1			
BLISSVILLE ROAD (TH-6)	1	1			
EAST CREEK DRIVE (TH-69)	1	1			
PARK STREET (TH-38)	2	2			
FARR DRIVE (TH-75)	1	1			
COREY LANE (TH-74)	1	1			
DRAKE ROAD (TH-24)	1	1			
VT. ROUTE 30 (NORTH)	2	1	2		1-PCMS
VT. ROUTE 30 (SOUTH)	2	1	2		1-PCMS
PATRICIA LANE (TH-72)	1	1			
SAND HILL ROAD (TH-42)	1	1			
VT. ROUTE 4A - END PROJECT	2	1	2		1-PCMS
FOURTH STREET (TH-8)	1	1			
U.S. ROUTE 4 ON RAMP		1			
U.S. ROUTE 4 OFF RAMP	1				
FAIR HAVEN STATE HIGHWAY	2	1	2		1-PCMS
TOTAL	22	18	8	1	4-PCMS

- NH HES 020-(K2) FAIR HAVEN
- STP HES 2614(I)S FAIR HAVEN - CASTLETON
- STP 2615(I)S FAIR HAVEN CLASS I

CONSTRUCTION AREA

NOTES:

1. SEE VAOT STD. E-100 FOR ADDITIONAL SIGN PLACEMENT DETAILS.
2. CONSTRUCTION ZONE SIGN LAYOUT SHALL BE IN ACCORDANCE WITH SECTION 6 OF THE LATEST EDITION OF THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD).
3. CONSTRUCTION SIGNS SHALL BE IN NEW OR LIKE NEW CONDITION PER VAOT STANDARDS.
4. DIAMOND SHAPED SIGNS SHALL BE 4' X 4' WITH BLACK LEGEND ON FLUORESCENT ORANGE BACKGROUND.
5. RETROREFLECTIVE SIGN SHEETING SHALL BE MINIMUM TYPE VII FOR ALL SOLID SUBSTRATE SIGNS AND MINIMUM TYPE VI FOR ALL ROLL-UP SIGNS.
6. ALL SIGN STANDS AND POST INSTALLATIONS SHALL BE NATIONAL COOPERATIVE HIGHWAY RESEARCH PROGRAM REPORT (NCHRP) 350 COMPLIANT.
7. THERE SHALL BE NO LANE CLOSURES ON THE U.S. ROUTE 4 NY APPROACH FROM 3:00 PM TO 7:00 PM, MONDAY THROUGH FRIDAY.
8. PORTABLE CHANGEABLE MESSAGE SIGNS ARE TO BE USED AS DIRECTED BY THE RESIDENT ENGINEER.
9. PAYMENT FOR CONSTRUCTION SIGNING WILL BE MADE UNDER ITEM 641.0 TRAFFIC CONTROL (HES 020-(K2)), ITEM 641.0 TRAFFIC CONTROL (STP HES 2614(I)S) AND ITEM 641.0 TRAFFIC CONTROL (STP 2615(I)S).

NOT TO SCALE

COMPOSITE TRAFFIC CONTROL PLAN SHEET	PROJECT NAME: FAIR HAVEN - CASTLETON & FAIR HAVEN	PLOT DATE: 22-FEB-2012 12:46
	PROJECT NUMBER: STP HES 2614(I)S, STP 2615(I)S, NH HES 020-(K2) & STP SRN (004)	DRAWN BY: C.A.K.
	FILE NAME: p06c058.dgn	CHECKED BY: D.E.G.
	PROJECT LEADER: D.E.G.	SHEET 11 OF 157