

QUANTITY SHEET 3

STP 2614(I)S					SUMMARY OF ESTIMATED QUANTITIES						DETAILED SUMMARY OF QUANTITIES				DETAILED SUMMARY OF QUANTITIES			
FULL C.E.	NON-PARTICIPATING	EMPLOYEE TRAINEESHIP	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS			
				114,700	114,700	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.									
				108,300	108,300	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.									
				600	600	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.									
				158	158	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.									
				400	400	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST.									
				4	4	EA	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712										
				4100	4100	EA	LINE STRIPING TARGETS	646.76	EST.									
				50	50	SY	GEOTEXTILE UNDER STONE FILL	649.31	EST.									
				50	50	LB	SEED	651.15	EST.									
				400	400	LB	FERTILIZER	651.18	EST.									
				1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.									
				50	50	CY	TOPSOIL	651.35	EST.									
				6350	6350	SY	TEMPORARY EROSION MATTING	653.20	EST.									
				971	971	SF	TRAFFIC SIGNS, TYPE A	675.20	0.97									
				20	20	SF	TRAFFIC SIGNS, TYPE B	675.21										
				1950	1950	LB	TUBULAR STEEL SIGN POST	675.33	44									
				620	620	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	14									
				6	6	EA	FOUNDATION FOR TUBULAR STEEL POST	675.43										
				278	278	EA	REMOVING SIGNS	675.50										
				17	17	EA	ERECTING SALVAGED SIGNS	675.60										
				10	10	EA	DELINEATOR WITH STEEL POST	676.10										
				500	500	LF	VEHICLE LOOP DETECTOR	678.22	23									
				1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50										
				1	1	LS	SPECIAL PROVISION (PAVED RAIL-HIGHWAY CROSSING) (VT. 4A-AARDOT 248-940C)	900.645										
				1	1	LS	SPECIAL PROVISION (RECONSTRUCT RAIL-HIGHWAY CROSSING) (VT. 4A-AARDOT 248-953D)	900.645										
				1	1	LS	SPECIAL PROVISION (TRAFFIC CONTROL, RAIL-HIGHWAY CROSSING) (AARDOT 248-940C)	900.645										
				1	1	LS	SPECIAL PROVISION (TRAFFIC CONTROL, RAIL-HIGHWAY CROSSING) (AARDOT 248-953D)	900.645										
				3100	3100	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	24									

PROJECT NAME: FAIR HAVEN - CASTLETON
 PROJECT NUMBER: STP HES 2614(I)S
 FILE NAME: p06c058.dgn PLOT DATE: 22-FEB-2012 12:46
 PROJECT LEADER: D.E.G. DRAWN BY: C.A.K.
 DESIGNED BY: M.J.M. CHECKED BY: D.E.G.
 IPARM FILE: p06c058qs3.i SHEET 18 OF 157