ITEM DETAIL SUMMARY SHEET #2

LOCATION			GUARDRAIL (GALVANIZED)							SIDEWALK					MISCELLANEOUS					REMARKS
BEGIN STATION	END STATION	POS.	616.35 TREATED TIMBER CURB LF	621.20 STEEL BEAM GUARDRAIL, GALVANIZED LF	621.21 HD STEEL BEAM GUARDRAIL, GALVANIZED LF	621.50 MANUFACTURED TERMINAL SECTION, FLARED EA	621.53 TERMINAL CONNECTOR FOR S.B. GUARDRAIL EA	621.60 ANCHOR FOR STEEL BEAM GUARDRAIL EA	621.80 REMOVAL AND DISPOSAL OF GUARDRAIL EA	203.15 COMMON EXCAV. CY	301.40 SUBBASE, RAP TON	616.28 CAST-IN-PLACE CONC. CURB, TYPE B LF	618.10 P.C.C. SIDEWALK, 5 INCH SY	618.30 DETECTABLE WARNING SURFACE SF	604.412 REHAB, DI, CB, MH CLASS I EA	604.415 REHAB, DI, CB, MH CLASS II EA	604.418 REHAB, DI, CB, MH CLASS III EA	616.47 BIT. CONC. GUT. & TRAF. ISLAND TON	676.10 DELINEATOR WITH STEEL POST EA	
FAIR HAVEN HIGHWAY: (DUTTON AVENUE)																				
0+75.0	10+30.0	LT/RT													3	3	3			SHALL BE PERFORMED AS DIRECTED BY THE RESIDENT ENGINEER
0+65.0		LT												10.0						CONSTRUCT DETECTABLE WARNING SURFACE.
1+20.0		LT												10.0						CONSTRUCT DETECTABLE WARNING SURFACE.
1+32.0		RT												10.0						CONSTRUCT DETECTABLE WARNING SURFACE.
16+03.5	18+91.0	LT	25.0	250.0		1			277.0										1	INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED FROM STA 16+03.5 TO STA 16+41.0. INSTALL NEW TREATED TIMBER CURB FROM STA 18+61.0 TO STA 18+86.0.
16+96.0	18+71.0	RT	25.0	137.5		1			178.0										1	INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED FROM STA 16+96.0 TO STA 17+33.5. INSTALL NEW TREATED TIMBER CURB FROM STA 18+70.0 TO STA 18+95.0.
20+82.0	22+07.0	LT	137.5	125.0					125.0											INSTALL NEW TREATED TIMBER CURB FROM STA 20+95.5 TO STA 22+33.0.
20+93.0	20+95.0	LT																0.4		CONSTRUCT BITUMINOUS CONCRETE GUTTER. SEE BITUMINOUS CONRETE GUTTER & TRAFFIC ISLAND ON SHEET 14.
21+03.5	21+05.5	RT																0.4		CONSTRUCT BITUMINOUS CONCRETE GUTTER. SEE BITUMINOUS CONRETE GUTTER & TRAFFIC ISLAND ON SHEET 14.
21+15.0	22+18.0	RT	137.5	103.0					103.0											INSTALL NEW TREATED TIMBER CURB FROM STA 21+05.5 TO STA 22+43.0
24+37.0	27+12.0	LT		237.5		1			266.0										1	INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED FROM STA 26+74.5 TO STA 27+12.0.
24+61.0	26+24.0	RT		287.5		1			313.0										1	INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED FROM STA 26+24.0.
FAIR HAVEN: (WELCOME CENTER)																				
W5+24.0		LT								4.0	4.4	14.0	13.4	27.0						CONSTRUCT SIDEWALK RAMP TYPE 6 WITH DETECTABLE WARNING SURFACE.
SHEET SUBTOTAL:			325.0	1140.5	-	4	-	-	1262.0	4.0	4.4	14.0	13.4	57.0	3	3	3	0.8	4	
SHEET 19 SUBTOTAL:			-	1458.5	188.5	6	4	6	1712.7	9.6	10.8	42.0	31.8	30.0	5	5	5	37.7	6	
ROUNDING:			-	26.0	6.5	-	-	-	25.3	1.4	0.8	4.0	4.8	3.0	-	-	-	1.5	-	
TOTAL:			325.0	2625.0	195.0	10	4	6	3000.0	15.0	16.0	60.0	50.0	90.0	8	8	8	40.0	10	

ITEM DETAIL SUMMARY SHEET #2

PROJECT NAME: FAIR HAVEN - CASTLETON

PROJECT NUMBER: STP HES 2614(I)S

FILE NAME: p06c058.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06c058ids2.i

PLOT DATE: 22-FEB-2012 12:47
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 20 OF 157