STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 4

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) 1.75 lb/ft 1.88 | 2.0 lb/ft 2.16 | 2.5 lb/ft 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3 | 4.0 lb/ft 1.7 | 4.0 MOD lb/ft 1.7 | TUBULAR STEEL Ø (in) FOUNDATION | 3.0 lb/ft 7.6 | 3.5 lb/ft 9.0 | 4.0 lb/ft 10.8 | 5.0 lb/ft 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| FAIR HAVEN: 28+54.0, RT | LEGAL LOAD LIMIT 24,000 POUNDS | 1 | 24 | 30 | 5.00 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE VR-017 | | E-141 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 28+91.0, RT | SWAMP RD | | | | | | 1 | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. | - | - |
| | STOP 0041 1107 0054 | 1<br>1 | 30<br>6 | 30<br>10 | 6.25<br>0.42 | | | | | | | | | | | | | | | | | | | | | | | | | | | | BACK-TO-BACK<br>SIGN ID CODE R-1<br>SIGN ID CODE VD-700 | | E-143<br>E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 28+99.0, RT | | 1 | 48 | 24 | 8.00 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE W1-6 | | E-152 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 31+50.0, RT | 0041 1107 0060 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | X | | | X | | | | | | | | | | | | | | | SIGN ID CODE VD-700 | | E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 34+85.0, RT | R R | 1 | 36 | 36 | 7.10 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE W10-1 | | E-190 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 35+18.0, LT | | 1 | 30 | 30 | 6.25 | | | | | | 1 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE W1-10R | 70 | |
| | 35 M.P.H. | 1 | 18 | 18 | 2.25 | | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE W13-1 | | E-155 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 37+45.5, RT | | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE W10-12 | 70 | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | LF | LF | LF | LF 14 | LF 112 | LF | | EA. | LB | LB | LB | | LB | LB | LB | LB | | | | | | | | |
| **TOTALS** | | SF 44.69 | SF | EA. 1 | SF | | | | | | | LF | | | LF 126 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET #4**

PROJECT NAME: FAIR HAVEN - CASTLETON
PROJECT NUMBER: STP HES 2614(1)S

FILE NAME: p06c058.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06c058tss04.i

PLOT DATE: 22-FEB-2012 12:49
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 51 OF 157