STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	SQUARE STEEL ANCHOR	SQUARE STEEL SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
	SHEET 48 SUBTOTAL				51.19											84																			
	SHEET 49 SUBTOTAL				47.38	20.00	3									42							6	606										
	SHEET 50 SUBTOTAL				33.34										28	98																		
	SHEET 51 SUBTOTAL				44.69		1								14	112																		
	SHEET 52 SUBTOTAL				51.52										14	84																		
	SHEET 53 SUBTOTAL				38.92											56																		
	SHEET 54 SUBTOTAL				38.26										42	112																		
	SHEET 55 SUBTOTAL				30.81										14	84																		
	SHEET 56 SUBTOTAL				43.42		1									98																		
	SHEET 57 SUBTOTAL				42.67		1									98																		
	SHEET 58 SUBTOTAL				35.59		4									112																		
	SHEET 59 SUBTOTAL				37.51		2									98																		
	SHEET 60 SUBTOTAL				40.43		3								14	98																		
	SHEET 61 SUBTOTAL				90.95											56																		
	SHEET 62 SUBTOTAL				54.26											56																		
	SHEET 63 SUBTOTAL				68.68											70																		
	SHEET 64 SUBTOTAL				80.62		1									28																		
	SHEET 65 SUBTOTAL				29.85										14	98																		
	SHEET 66 SUBTOTAL				32.33										14	56																		
	SHEET 67 SUBTOTAL				46.52											126																		
	SHEET 68 SUBTOTAL				31.09		1								14	70																		
	SUBTOTAL				970.03	20.00	17								168	1736							6	606										
	ROUNDING				0.97	-	-								2	44							-	14										
												LF	LF	LF	LF 170	LF 1780	LF		EA.	LB	LB	LB		LB 620	LB	LB	LB							
TOTALS					SF 971	SF 20	EA. 17	SF				LF			LF 1950					LB			EA. 6	LB 620				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #22

PROJECT NAME: FAIR HAVEN - CASTLETON

PROJECT NUMBER: STP HES 2614(I)S

FILE NAME: p06c058.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06c058tss22.i

PLOT DATE: 22-FEB-2012 12:51
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 69 OF 157