



- NOTES:
1. LOCATION OF EXISTING ANCHOR BOLTS TO BE VERIFIED IN THE FIELD BY THE CONTRACTOR PRIOR TO ORDERING BRIDGE POSTS.
 2. POSTS SHALL BE SHOP CUT AND DRILLED PRIOR TO GALVANIZING.
 3. SEE STANDARD SHEET SB-R6-82 FOR ADDITIONAL BRIDGE RAILING DETAILS.
 4. NON-SHRINKING GROUT SHALL CONFORM TO SUBSECTION 707.03 MORTAR TYPE IV OF THE STANDARD SPECIFICATIONS. PACK UNDER BASE PLATE. PAYMENT WILL BE INCIDENTAL TO ITEM 525.60 BRIDGE RAILING REPAIR, TYPE III.
 5. NEW ARM A-449 7/8" DIAMETER BOLTS FOR SURFACE MOUNTED POSTS SHALL BE FURNISHED EACH WITH ONE NUT AND ONE WASHER.

BRIDGE DETAIL SHEET #2	PROJECT NAME: FAIR HAVEN - CASTLETON	
	PROJECT NUMBER: STP HES 2614(1)S	
	FILE NAME: p06c058.dgn	PLOT DATE: 22-FEB-2012 12:51
	PROJECT LEADER: D.E.G.	DRAWN BY: C.A.K.
DESIGNED BY: M.J.M.	CHECKED BY: D.E.G.	
IPARM FILE: p06c058br2.i	SHEET 73 OF 157	