QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP 2615(1)S

SUMMARY OF ESTIMATED QUANTITIES

FULL C.E.	BRIDGE	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		4	4	EA	TERMINAL CONNECTOR FOR STEEL BEAM GUARDRAIL	621.53	
		4	4	EA	ANCHOR FOR STEEL BEAM RAIL	621.60	
		150	150	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	9
		18	18	EA	ADJUST ELEVATION OF VALVE BOX	629.20	
		1000	1000	HR	UNIFORMED TRAFFIC OFFICER	630.10	EST.
		1500	1500	HR	FLAGGERS	630.15	EST.
0.33			0.33	LS	FIELD OFFICE, ENGINEERS	631.10	
0.33			0.33	LS	TESTING EQUIPMENT, CONCRETE	631.16	
0.33			0.33	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
0.2			0.2	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	
		0.2	0.2	LS	MOBILIZATION / DEMOBILIZATION	635.11	
		1	1	LS	TRAFFIC CONTROL (STP 2615(1)S)	641.10	
		1	1	LS	PUBLIC RELATIONS OFFICER	641.12	
		1	1	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
		22,600	22,600	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	42
		15,900	15,900	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	34
		475	475	LF	DURABLE 8 INCH WHITE LINE, THERMOPLASTIC	646.442	30
		60	60	LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	3
		125	125	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	6
		100	100	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	
		725	725	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	6
		45,200	45,200	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
		31,800	31,800	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
		250	250	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
		180	180	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
		1450	1450	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST.
		800	800	EA	LINE STRIPING TARGETS	646.76	EST.
		165	165	LF	PAINTED CURB	646.81	3
		50	50	LB	SEED	651.15	EST.
		400	400	LB	FERTILIZER	651.18	EST.
		1	1	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		50	50	CY	TOPSOIL	651.35	EST.
		293	293	SF	TRAFFIC SIGNS, TYPE A	675.20	0.85
		725	725	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	11
		81	81	EA	REMOVING SIGNS	675.50	
		18	18	EA	ERECTING SALVAGED SIGNS	675.60	
		1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	
		1625	1625	TON	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	13

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIR HAVEN

PROJECT NUMBER: STP 2615(1)S

FILE NAME: p06c060.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p06c060qs2.i

PLOT DATE: 22-FEB-2012 12:52
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 85 OF 157