



646.402 DURABLE 4 INCH WHITE LINE, THERMOPLASTIC
 (ALL LINES WILL INCLUDE EDGE LINE BREAKS AND RADIUS FOR TOWN HIGHWAYS)
 FAIR HAVEN:
 STA 108+00.00 - STA 113+00.00 LT & RT
 STA 108+00.00 - STA 108+38.00 NO PARKING ZONE, LT
 STA 108+18.00 - STA 108+38.00 NO PARKING ZONE, RT
 STA 108+84.00 - STA 109+51.00 NO PARKING ZONE, LT

646.602 TEMPORARY 4 INCH WHITE LINE, PAINT
 (ALL LINES WILL INCLUDE EDGE LINE BREAKS AND RADIUS FOR TOWN HIGHWAYS)
 FAIR HAVEN:
 STA 108+00.00 - STA 113+00.00 LT & RT
 STA 108+00.00 - STA 108+38.00 NO PARKING ZONE, LT
 STA 108+18.00 - STA 108+38.00 NO PARKING ZONE, RT
 STA 108+84.00 - STA 109+51.00 NO PARKING ZONE, LT

646.502 DURABLE CROSSWALK MARKING, THERMOPLASTIC
 FAIR HAVEN:
 STA 108+42.00 LT/RT
 STA 108+71.52 LT, TH-4I
 646.702 TEMPORARY CROSSWALK MARKING, PAINT
 FAIR HAVEN:
 STA 108+42.00 LT/RT
 STA 108+71.52 LT, TH-4I
 675.50 REMOVING SIGNS
 AS SHOWN - 5
 675.60 ERECTING SALVAGED SIGNS
 AS SHOWN - 2

646.412 DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC
 (ALL LINES WILL INCLUDE C/L BREAKS FOR TOWN HIGHWAYS) S=SOLID, D=DASHED
 FAIR HAVEN:
 STA 108+00.00 - STA 113+00.00 LT @ RT
 STA 108+71.52 DOUBLE SOLID LT, TH-4I

646.612 TEMPORARY 4 INCH YELLOW LINE, PAINT
 (ALL LINES WILL INCLUDE C/L BREAKS FOR TOWN HIGHWAYS) S=SOLID, D=DASHED
 FAIR HAVEN:
 STA 108+00.00 - STA 113+00.00 LT @ RT
 STA 108+71.52 DOUBLE SOLID LT, TH-4I

646.482 DURABLE 24 INCH STOP BAR, THERMOPLASTIC
 FAIR HAVEN:
 STA 108+71.52 LT, TH-4I

646.682 TEMPORARY 24 INCH STOP BAR, PAINT
 FAIR HAVEN:
 STA 108+71.52 LT, TH-4I

646.492 DURABLE LETTER OR SYMBOL, THERMOPLASTIC
 FAIR HAVEN:
 STA 108+71.52 LT, TH-4I "S,T,O,P" (4 EA)
 STA 110+34.80 RT, "S,T,O,P" (4 EA)
 STA 110+75.20 RT, "A,H,E,A,D" (5 EA)

646.692 TEMPORARY LETTER OR SYMBOL, PAINT
 FAIR HAVEN:
 STA 108+71.52 LT, TH-4I "S,T,O,P" (8 EA)
 STA 110+34.80 RT, "S,T,O,P" (8 EA)
 STA 110+75.20 RT, "A,H,E,A,D" (10 EA)

604.42 CHANGING ELEVATION OF SEWER MANHOLES
 FAIR HAVEN:
 STA 108+74.0 RT
 STA 111+76.0 LT
 629.20 ADJUST ELEVATION OF VALVE BOX
 FAIR HAVEN:
 STA 108+74.0 LT
 STA 108+77.0 LT
 STA 108+80.0 LT

604.412 604.415 OR 604.418
 REHAB. DROP INLETS, CATCH BASINS OR MANHOLES (SEE NOTE 2)
 FAIR HAVEN:
 STA 110+71.0 LT
 STA 110+71.0 RT
 STA 112+09.0 RT
 STA 112+42.0 LT

NOTES:
 1. PAVING LIMIT ON ALL TOWN HIGHWAYS SHALL BE MEASURED 25 FT BACK FROM VT. ROUTE 4A EDGE OF SHOULDER UNLESS DENOTED OTHERWISE ON THE PLANS OR AS DIRECTED BY THE RESIDENT ENGINEER.
 2. THE CONTRACTOR SHALL REHAB. THE EXISTING DROP INLETS, CATCH BASINS OR MANHOLES TO A DEPTH AS DIRECTED BY THE RESIDENT ENGINEER. ALL REHAB. WORK WILL BE PAID FOR UNDER THE APPLICABLE REHAB. ITEM AS DIRECTED BY THE RESIDENT ENGINEER. ALL EXISTING UTILITIES MARKED "TO REMAIN" SHALL NOT BE ALTERED OR REHABILITATED UNLESS DIRECTED OTHERWISE BY THE RESIDENT ENGINEER.

SIGN LEGEND
 R = REMOVE
 S = SALVAGE
 N = NEW
 RET = RETAIN
 B-B = BACK TO BACK
 EXISTING = - - - - -
 NEW = _____

NOT TO SCALE

PROJECT LAYOUT SHEET #13

| | |
|------------------------------|------------------------------|
| PROJECT NAME: FAIR HAVEN | PLOT DATE: 22-FEB-2012 12:53 |
| PROJECT NUMBER: STP 2615(1)S | DRAWN BY: C.A.K. |
| FILE NAME: p06c060.dgn | CHECKED BY: D.E.G. |
| DESIGNED BY: M.J.M. | SHEET 100 OF 157 |
| IPARM FILE: p06c0601013.i | |