QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

NH HES 020-1(21)

SUMMARY OF ESTIMATED QUANTITIES

EPSC	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO	ROUNDING
		3	3	EA	THINNING AND TRIMMING FOR SIGNS	201.31	
		840	840	CY	COMMON EXCAVATION	203.15	2.6
		555	555	CY	EARTH BORROW	203.30	4
		1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
		40,800	40,800	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	29
		4800	4800	LF	MILLED RUMBLE STRIPS	213.10	75
		200	200	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	2.8
		10	10	TON	AGGREGATE SHOULDERS	402.12	5
		250	250	TON	AGGREGATE SHOULDERS, RAP	402.13	26
		170	170	CWT	EMULSIFIED ASPHALT	404.65	5
		1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	
					BEGIN OPTION AA		
		4650	4650	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0.0% RAP CONTENT)	490.30	20
		4650	4650	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0.0% < RAP CONTENT < 15.0%)	490.30	20
		4650	4650	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% <= RAP CONTENT < 25.0%)	490.30	20
		4650	4650	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% <= RAP CONTENT <= 50.0%)	490.30	20
					END OPTION AA		
		1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	
		20	20	HR	POWER GRADER RENTAL	608.15	EST.
		10	10	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
		10	10	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
		15	15	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
		15	15	HR	TRUCK RENTAL	608.37	EST.
		25	25	HR	LOADER RENTAL, TYPE I	608.40	EST.
		200	200	LF	GRANITE SLOPE EDGING	616.20	
		145	145	LF	REMOVAL OF EXISTING CURB	616.41	4
		25	25	TON	BITUMINOUS CONCRETE GUTTERS AND TRAFFIC ISLANDS	616.47	1.8
		5	5	EA	YIELDING MARKER POSTS	619.17	EST.
		1	1	EA	MANUFACTURED TERMINAL SECTION, FLARED	621.50	
		580	580	LF	REMOVE AND RESET GUARDRAIL	621.75	5
		40	40	LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	2.5

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING BITUMINOUS PAVEMENT
39,538	SY	MAINLINE
1233	SY	APPROACHES
29	SY	ROUNDING
40,800	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
1153	TON	LEVELING COURSE (TYPE IVS)
3463	TON	WEARING COURSE (TYPE IIIS)
7	TON	BASE COURSE (TYPE IIS)
7	TON	BINDER COURSE (TYPE IIS)
20	TON	ROUNDING
4650	TON	TOTAL
		AGGREGATE SHOULDERS
5	TON	END SECTION
5	TON	ROUNDING
10	TON	TOTAL
		AGGREGATE SHOULDERS, RAP
224	TON	TREATED TIMBER CURB
26	TON	ROUNDING
250	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIR HAVEN

PROJECT NUMBER: NH HES 020-1(21)

FILE NAME: 08b234.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
DWG. NO. 08b234qsl.i

PLOT DATE: 22-FEB-2012 12:5
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 120 OF 157