QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

NH HES 020-1(21)

SUMMARY OF ESTIMATED QUANTITIES

EPSC	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO	ROUNDING
		400	400	HR	UNIFORMED TRAFFIC OFFICERS	630.10	
		600	600	HR	FLAGGERS	630.15	
	0.33		0.33	LS	FIELD OFFICE, ENGINEERS	631.10	
	0.33		0.33	LS	TESTING EQUIPMENT, CONCRETE	631.16	
	0.33		0.33	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	
	0.2		0.2	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25	
		0.2	0.2	LS	MOBILIZATION / DEMOBILIZATION	635.11	
		1	1	LS	TRAFFIC CONTROL (NH HES 020-1(21))	641.10	
		3	3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	
		400	400	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	34
		300	300	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	22
		7150	7150	LF	DURABLE 6 INCH WHITE LINE, RECESSED POLYUREA	646.426	13
		4700	4700	LF	DURABLE 6 INCH YELLOW LINE, RECESSED POLYUREA	646.436	49
		20	20	LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	3
		550	550	LF	DURABLE 12 INCH WHITE LINE, RECESSED POLYUREA	646.466	13
		430	430	LF	DURABLE 12 INCH YELLOW LINE, RECESSED POLYUREA	646.476	15
		15	15	LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482	3
		19	19	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492	
		800	800	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
		600	600	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
		14,200	14,200	LF	TEMPORARY 6 INCH WHITE LINE, PAINT	646.622	EST.
		9400	9400	LF	TEMPORARY 6 INCH YELLOW LINE, PAINT	646.632	EST.
		175	175	LF	TEMPORARY 12 INCH WHITE LINE, PAINT	646.662	EST.
		30	30	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
		38	38	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
		300	300	EA	LINE STRIPING TARGETS	646.76	EST.
		200	200	LF	PAINTED CURB	646.81	3
725			725	SY	GEOTEXTILE SILT FENCE	649.51	15
		50	50	LB	SEED	651.15	EST.
		400	400	LB	FERTILIZER	651.18	EST.
		2	2	TON	AGRICULTURAL LIMESTONE	651.20	EST.
		185	185	CY	TOPSOIL	651.35	1.1
1			1	LS	EPSC PLAN	652.10	
50			50	HR	MONITORING OF EPSC PLAN	652.20	EST.
1			1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	
8			8	EA	INLET PROTECTION DEVICE, TYPE I	653.40	
2650			2650	LF	PROJECT DEMARCATION FENCE	653.55	26

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: FAIR HAVEN

PROJECT NUMBER: NH HES 020-1(21)

FILE NAME: 08b234.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
DWG. NO. 08b234qs2.i

PLOT DATE: 22-FEB-2012 12:59
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 121 OF 157