ITEM DETAIL SUMMARY SHEET

LOCATION			MISCELLANEOUS											REMARKS
BEGIN STATION	END STATION	POS.	203.15 COMMON EXCAVATION CY	203.30 EARTH BORROW CY	301.28 SUBBASE OF CRUSHED GRAVEL FINE GRADED TON	616.20 GRANITE SLOPE EDGING LF	616.41 REMOVAL OF EXSTING CURB LF	616.47 BIT. CONC. GUTTER & TRAFFIC ISLAND TON	621.50 MANUF. TERM. SECT., FLARED EA	621.75 REMOVE & RESET GUARDRAIL LF	621.80 REMOVAL & DISPOSAL GUARDRAIL LF	651.35 TOPSOIL CY	676.10 DELINEATOR W/STEEL POST EA	
U.S. ROUTE 4:														
4+02.0	12+85.0	LT	358.1	268.6								89.6		PAVEMENT REMOVAL ALONG U.S. ROUTE 4 JUG HANDLE IN FAIR HAVEN.
4+07.0	6+74.0	RT	28.3	21.2								7.1		PAVEMENT REMOVAL ALONG U.S. ROUTE 4 SHOULDER IN FAIR HAVEN.
6+12.0	6+93.0	RT	102.6		197.2	200.0	141.0	23.2						REMOVE EXISTING BITUMINOUS CONCRETE TRAFFIC ISLAND. CONSTRUCT NEW BITUMINOUS CONCRETE TRAFFIC ISLAND. SEE BITUMINOUS CONCRETE GUTTER AND TRAFFIC ISLAND DETAIL ON SHEET 146.
9+29.0	16+93.0	RT	177.4	133.1								44.4		PAVEMENT REMOVAL ALONG U.S. ROUTE 4 SHOULDER IN FAIR HAVEN.
10+87.0	12+87.0	LT								200.0				
11+70.0	15+82.5	RT							1	375.0	37.5		1	INSTALL NEW MANUFACTURED TERMINAL SECTION, FLARED FROM STA 15+45.0 TO STA 15+82.5.
17+35.0	25+10.0	RT	171.0	128.3								42.8		PAVEMENT REMOVAL ALONG U.S. ROUTE 4 SHOULDER IN FAIR HAVEN.
ROUNDING:			2.6	3.8	2.8	-	4.0	1.8	-	5.0	2.5	1.1	-	
TOTAL:			840.0	555.0	200.0	200.0	145.0	25.0	1	580.0	40.0	185.0	1	

ITEM DETAIL SUMMARY SHEET

PROJECT NAME: FAIR HAVEN

PROJECT NUMBER: NH HES 020-1(21)

FILE NAME: 08b234.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
DWG. NO. 08b234ids.i

PLOT DATE: 22-FEB-2012 12:5
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 123 OF 157