

QUANTITY SHEET 1

STP SRIN(004)						SUMMARY OF ESTIMATED QUANTITIES					DETAILED SUMMARY OF QUANTITIES			DETAILED SUMMARY OF QUANTITIES		
				FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING	QUANTITIES	UNIT	ITEMS	QUANTITIES	UNIT	ITEMS
					20	20	CY	COMMON EXCAVATION	203.15	0.7						
					20	20	CY	TRENCH EXCAVATION	204.20				SUPERPAVE BITUMINOUS CONCRETE PAVEMENT			
					1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				2	TON	BASE COURSE (TYPE IS)	
					24	24	TON	SUBBASE CRUSHED GRAVEL, FINE GRADED	301.28	0.5			2	TON	TOTAL	
					1	1	LS	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50							
								BEGIN OPTION BB								
					2	2	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0.0% RAP CONTENT)	490.30							
					2	2	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (0.0% < RAP CONTENT < 15.0%)	490.30							
					2	2	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (15.0% <= RAP CONTENT < 25.0%)	490.30							
					2	2	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (25.0% <= RAP CONTENT <= 50.0%)	490.30							
								END OPTION BB								
								BEGIN OPTION CC								
					28	28	LF	18" CSP .064 (2 2/3" x 1/2")	601.0015							
					28	28	LF	18" CPEP (SL)	601.2615							
								END OPTION CC								
					2	2	EA	CONCRETE CATCH BASIN WITH CAST IRON GRATE	604.10							
					1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412							
					1	1	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415							
					120	120	LF	VERTICAL GRANITE CURB	616.21							
					71	71	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	0.7						
					20	20	SF	DETECTABLE WARNING SURFACE	618.30							
					100	100	HR	UNIFORMED TRAFFIC OFFICERS	630.10							
					150	150	HR	FLAGGERS	630.15							
				0.1		0.1	LU	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.25							
					12	12	EA	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492							
					35	35	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	4.5						
					24	24	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692							
					70	70	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702							
					77	77	SF	TRAFFIC SIGNS, TYPE A	675.20							
					150	150	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	10						
					12	12	EA	REMOVING SIGNS	675.50							
					1	1	EA	ERECTING SALVAGED SIGNS	675.60							
					2	2	EA	SPECIAL PROVISION (SOLAR-POWERED SCHOOL ZONE FLASHING BEACON)	900.620							

PROJECT NAME: FAIR HAVEN	
PROJECT NUMBER: STP SRIN (004)	
FILE NAME: p06c058.dgn	PLOT DATE: 22-FEB-2012 12:5
PROJECT LEADER: D.E.G.	DRAWN BY: C.A.K.
DESIGNED BY: M.J.M.	CHECKED BY: D.E.G.
IPARM FILE: p06c058qsl.i	SHEET 148 OF 157