STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
MIDDLEBURY: 62+29.0, LT	JCT	1	21	15	2.19						1					16.0 X		X																SIGN ID CODE M2-1		SHS
	7	1	24	24	4.00																													SIGN ID CODE MI-4		SHS
64+72.0, LT		1	36	36	9.00						2					14.33 X 14.50		X																SIGN ID CODE W3-1		SHS
68+09.0, RT	EAST MIDDLEBURY RIPTON 4	1	30	18	3.75						1					12.42 X		X																SIGN ID CODE VD-18		E-128B
71+94.0, RT		1	36	36	9.00						2					11.67 X 11.83		X																SIGN ID CODE W3-1		SHS
77+15.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					14.33 X		X																SIGN ID CODE VR-017		E-141
77+53.0, RT	WILMAR RD / MAIN ST						1 1				1					13.50 X		X																SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 1250 0111 0146	1 1	30 6	30 10	6.25 0.42																													BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138
83+14.0, RT	CHURCH ST						1				1					14.33 X		X																SALVAGED SIGNS TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 1250 0111 0158	1 1	30 6	30 10	6.25 0.42																													BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138
	ALL WAY	1	18	6	0.75																													SIGN ID CODE RI-4		SHS
												LF	LF	LF	LF	LF ~~126~~ 122.91	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 47.03	SF	EA. 3	SF				LF			LF ~~126~~ 122.91					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #2

PROJECT NAME: MIDDLEBURY
PROJECT NUMBER: STP 2627(I)

FILE NAME: p06c222.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06c222tss02.i

PLOT DATE: 19-SEP-2013 11:14
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 37 OF 114