STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
	SHEET 36 SUBTOTAL				79.99		-									95.83 ~~84~~							2	~~211~~ 250.8											
	SHEET 37 SUBTOTAL				47.03		3									122.91 ~~126~~							-	-											
	SHEET 38 SUBTOTAL				42.51		5									97.5 ~~98~~							-	-											
	SHEET 39 SUBTOTAL				37.84		~~5~~ 4									86.08 ~~84~~							-	-											
	SHEET 40 SUBTOTAL				39.26		7									77.16 ~~84~~							-	-											
	SHEET 41 SUBTOTAL				30.67		5									102.09 ~~126~~							-	-											
	SHEET 42 SUBTOTAL				45.25		-									170.59 ~~196~~							-	-											
	SHEET 43 SUBTOTAL				30.05		3									105.37 ~~98~~							-	-											
	SHEET 44 SUBTOTAL				49.67		1									168.16 ~~182~~							-	-											
	SHEET 45 SUBTOTAL				51.92		-									112.5 ~~112~~							-	-											
93+40 LT							8									1 @ 15.58 1 @ 15.42																			
94+38 RT	CROSSWALK DIAGONAL ARROW															1 @ 14.75																			
94+38 LT	PED CROSSING															1 @ 14.83																			
96+68 RT							4									1 @ 15.25 1 @ 15.08																			
199+24 RT	1250 MM / 0111 X 0384						1									1 @ 9.67																			
	ROUNDING				0.81		-									35							-	14											
												LF	LF	LF	LF	LF ~~1225~~	LF		EA.	LB	LB	LB		LB 225	LB	LB	LB								
	TOTALS				SF ~~455~~ 474.94	SF	EA. ~~29~~ 41	SF				LF				LF ~~1225~~ 1238.77				LB			EA. 2	LB ~~225~~ 250.8				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #11

PROJECT NAME: MIDDLEBURY
PROJECT NUMBER: STP 2627(1)

FILE NAME: p06c222.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06c222tss11.i

PLOT DATE: 19-SEP-2013 11:15
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 46 OF 114