STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 8

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
RIPTON: 67+00.0, LT	RIPTON ELEM. SCHOOL →	1	72	20	10.00						2					X		X															SIGN ID CODE DI-2R		E-123
	• 67+25 ~ 69+75 LT CHEVRONS REPLACED BY 6" WHITE DELINEATORS																																		
67+25.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
67+65.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
68+25.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
68+50.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
68+75.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
69+50.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
69+75.0, LT		1 1	~~18~~ 6 ~~18~~ 6	~~24~~ 8 ~~24~~ 8	~~3.00~~ 0.33 ~~3.00~~ 0.33						2					X		X															SIGN ID CODE WI-8R SIGN ID CODE WI-8L		SHS SHS
												LF	LF	LF	LF	LF 224	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 52.00	SF	EA.	SF				LF			LF 224					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #8

PROJECT NAME: RIPTON - HANCOCK

PROJECT NUMBER: STP 2803(I)

FILE NAME: p08c160.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p08c160tss08.i

PLOT DATE: 19-SEP-2013 11:16
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 104 OF 114