STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
RIPTON: 219+29.0, LT	WEST	1	24	12	2.00						1					X		X														SIGN ID CODE M3-4		E-136B
	SCENIC	1	30	15	3.13																											SIGN ID CODE VM-064	113	
	VERMONT 125	1	30	24	5.00																											SIGN ID CODE MI-4		E-136B
240+57.0, LT	HIDDEN DRIVE RIGHT	1	30	30	6.25						2					X		X														SIGN ID CODE VW-054		E-154
		1	30	30	6.25																											SIGN ID CODE W11-2 SIGN SHALL BE FLUORESCENT YELLOW GREEN.		SHS
	NEXT 1500 FT	1	6	10	0.42																											SIGN ID CODE W16-4 SIGN SHALL BE FLUORESCENT YELLOW GREEN.		SHS
256+22.0, RT	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					X		X														SIGN ID CODE VR-017		E-141
256+56.0, RT	BROOKS RD						1				1					X		X														SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKETS REQUIRED TO INSTALL SALVAGED SIGNS ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	-	-
	STOP 1250 0116 0486	1 1	30 6	30 10	6.25 0.42																											BACK-TO-BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		SHS E-138
258+76.0, RT	MOOSE CROSSING	1	30	30	6.25						1					X		X														SIGN ID CODE VW-000		E-153
	STAY ALERT	1	18	18	2.25																												113		
												LF	LF	LF	LF	LF 84	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS			SF 43.22	SF	EA. 1	SF						LF			LF 84					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #14

PROJECT NAME: RIPTON - HANCOCK

PROJECT NUMBER: STP 2803(I)

FILE NAME: p08cl60.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p08cl60tssl4.i

PLOT DATE: 19-SEP-2013 11:16
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 110 OF 114