STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 15

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS SHS = FHWA STANDARD SIGNS BOOK	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
RIPTON: 286+04.0, LT	MOOSE CROSSING	1	30	30	6.25						1					X		X															SIGN ID CODE VW-000		E-153
	STAY ALERT	1	18	18	2.25																													113	
HANCOCK: 0+00.0, RT	HANCOCK / RIPTON	1	72	10	5.00						2					X		X																113	
	1250 0108 0000 / 1250 0116 0579	1 1	6 6	10 10	0.42 0.42																												SIGN ID CODE VD-700 SIGN ID CODE VD-700		E-138 E-138
9+19.0, RT	Snow Bowl 1000 FT NEXT RIGHT	1	54	36	13.50						2					X		X																113	
10+51.0, LT	MOOSE CROSSING	1	30	30	6.25						1					X		X																SIGN ID CODE VW-000		E-153
	NEXT 4 MILES	1	24	18	3.00																												SIGN ID CODE W7-3a		SHS
	1250 0108 0020						1																											-	-
17+70.0, RT	SNOW BOWL →	1	72	12	6.00						2					X		X																SIGN ID CODE DI-1		E-123
19+90.0, RT	←	1	48	24	8.00						2					X		X																SIGN ID CODE W1-6L		SHS
												LF	LF	LF	LF	LF 140	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 51.09	SF	EA. 1	SF							LF			LF 140					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #15

PROJECT NAME: RIPTON - HANCOCK

PROJECT NUMBER: STP 2803(I)

FILE NAME: p08cl60.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.M.
IPARM FILE: p08cl60tssl5.i

PLOT DATE: 19-SEP-2013 11:16
DRAWN BY: C.A.K.
CHECKED BY: D.W.E.
SHEET 111 OF 114