COMPOSITE QUANTITY SHEET 3

STATE OF VERMONT
AGENCY OF TRANSPORTATION

STP 2629(I)			STP EH 08(13)			SUMMARY OF ESTIMATED QUANTITIES				
EMPLOYEE TRAINEESHIP	FULL C.E.	ROADWAY	FULL C.E.	EROSION CONTROL	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		110				110	LB	SEED	651.15	
		400				400	LB	FERTILIZER	651.18	
		1				1	TON	AGRICULTURAL LIMESTONE	651.20	
		1				1	TON	HAY MULCH	651.25	
		100				100	CY	TOPSOIL	651.35	
				1		1	LS	EPSC PLAN	652.10	
				56		56	HR	MONITORING EPSC PLAN	652.20	
				1		1	LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	
		3700		180		3880	SY	TEMPORARY EROSION MATTING	653.20	
				11		11	EA	INLET PROTECTION DEVICE, TYPE I	653.40	
				700		700	LF	PROJECT DEMARCATION FENCE	653.55	
				4300		4300	LF	EROSION LOGS	653.60	
		69				69	SF	TRAFFIC SIGNS, TYPE A	675.20	
		325				325	LF	SQUARE STEEL SIGN POST AND ANCHOR	675.341	
		45				45	EA	REMOVING SIGNS	675.50	
		18				18	EA	ERECTING SALVAGED SIGNS	675.60	
		10				10	EA	DELINEATOR WITH STEEL POST	676.10	
		1				1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	
		3300				3300	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	
		54,000				54,000	SY	SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)	900.675	
		750				750	TON	SPECIAL PROVISION (PORTLAND CEMENT FOR BASE STABILIZATION)	900.680	
		700				700	CWT	SPECIAL PROVISION (FOG SEAL SURFACE TREATMENT)	900.683	

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES		
QUANTITIES	UNIT	ITEMS

COMPOSITE QUANTITY SHEET #3

PROJECT NAME: WHITING - MIDDLEBURY & CORNWALL - MIDDLEBURY

PROJECT NUMBER: STP 2629(I) & STP EH08(13)

FILE NAME: p06c226.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
DWG. NO. p06c266cquan3.i

PLOT DATE: 30-MAR-2012 14:12
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 5 OF 133