QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

EMPLOYEE TRAINEESHIP	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		300	300	CY	COMMON EXCAVATION	203.15	16
		425	425	CY	EARTH BORROW	203.30	22
		1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
		4300	4300	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	18
		2400	2400	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	38
		150	150	CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	20
		54,000	54,000	SY	RECLAIMED STABLIZED BASE	310.20	358
		3100	3100	TON	AGGREGATE SHOULDERS	402.12	10
		600	600	CWT	EMULSIFIED ASPHALT	404.65	32
		1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	
		34,500	34,500	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	460
		1	1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	
		1	1	LU	MAT DENSITY PAY ADJUSTMEMT (N.A.B.I.)	490.32	
		1	1	LU	SURFACE TOLERANCE PAY ADJUSTMENT (N.A.B.I.)	490.33	
		1	1	LU	LONGITUDINAL JOINT COMPACTION PAY ADJUSTMENT (N.A.B.I.)	490.34	
		300	300	HR	POWER GRADER RENTAL	608.15	EST.
		75	75	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
		100	100	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
		50	50	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
		125	125	HR	TRUCK RENTAL	608.37	EST.
		300	300	HR	LOADER RENTAL, TYPE I	608.40	EST.
		10	10	TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15	EST.
		150	150	EA	YIELDING MARKER POSTS	619.17	EST.

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		SPECIAL PROVISION (RECLAIMED STABILIZED BASE, PORTLAND CEMENT)
53,642	SY	MAINLINE
358	SY	ROUNDING
54,000	SY	TOTAL
		COLD PLANING, BITUMINOUS PAVEMENT
4282	SY	SIDE ROADS
18	SY	ROUNDING
4300	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
16,498	TON	WEARING COURSE (TYPE IVS)
7869	TON	LEVELING COURSE (TYPE IVS)
9387	TON	BASE COURSE (TYPE IIS)
482	TON	SIDE ROADS
39	TON	INTERSECTION RECONFIGURATIONS
15	TON	PULLOFFS
210	TON	ROUNDING
34,500	TON	TOTAL
		AGGREGATE SHOULDERS
3090	TON	BACKING UP SHOULDERS TO FULL HEIGHT
10	TON	ROUNDING
~~3100~~	TON	TOTAL
		TEMPORARY EROSION MATTING
250	TON	ITEM DETAIL SUMMARY SHEET
3005	TON	DITCH CLEANING DETAIL SHEET
394	TON	INTERSECTION RECONFIGURATIONS
51	TON	ROUNDING
~~3700~~	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: WHITING - MIDDLEBURY

PROJECT NUMBER: STP 2629(I)

FILE NAME: p06c226.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
DWG. NO. p06c226quant.i

PLOT DATE: 30-MAR-2012 14:13
DRAWN BY: C.A.K.
CHECKED BY: D.E.G.
SHEET 12 OF 133