QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

		NON PARTICIPATING	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		-	-	125	125	CY	COMMON EXCAVATION	203.15	1.5
		-	-	25	25	CY	UNCLASSIFIED EXCAVATION	203.17	EST.
		-	-	25	25	CY	EARTH BORROW	203.30	EST.
		-	-	1	1	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.
		2817	-	69,983	72,800	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	54
		-	-	550	550	TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	EST.
		12	-	288	300	GWT	EMULSIFIED ASPHALT	404.65	8
		-	-	1	1	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	EST.
		316	-	7734	8050	TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 70-28)	490.30	35
		-	-	1	1	LU	AIR VOID PAY ADJUSTMENT (N.A.B.I.)	490.31	EST.
		6	-	83	89	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-
		-	-	14	14	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-
		-	-	2	2	EA	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-
		3	-	19	22	EA	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-
		-	-	100	100	HR	POWER GRADER RENTAL	608.15	EST.
		-	-	75	75	HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.
		-	-	30	30	HR	POWER BROOM RENTAL, TYPE I	608.30	EST.
		-	-	200	200	HR	POWER BROOM RENTAL, TYPE II	608.31	EST.
		-	-	125	125	HR	TRUCK RENTAL	608.37	EST.
		-	-	100	100	HR	LOADER RENTAL, TYPE I	608.40	EST.
		-	-	750	750	LF	CAST IN PLACE CONCRETE CURB, TYPE B	616.28	22
		-	-	10	10	TON	BITUMINOUS CONCRETE GUTTERS & TRAFFIC ISLANDS	616.47	EST.
		-	-	405	405	SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	5.9
		-	-	550	550	SF	DETECTABLE WARNING SURFACE	618.30	10
		-	-	25	25	EA	YIELDING MARKER POSTS	619.17	-
		-	-	43	43	EA	ADJUST ELEVATION OF VALVE BOX	629.20	-
		200	-	1900	2100	HR	UNIFORMED TRAFFIC OFFICERS	630.10	-
		300	-	2800	3100	HR	FLAGGERS	630.15	-
		-	1	-	1	LS	TESTING EQUIPMENT, CONCRETE	631.16	EST.
		-	1	-	1	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	EST.
		-	-	1	1	LS	MOBILIZATION / DEMOBILIZATION	635.11	EST.
		-	-	1	1	LS	TRAFFIC CONTROL	641.10	EST.
		-	-	1	1	LS	PUBLIC RELATIONS OFFICER	641.12	-
		-	-	5	5	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		COLD PLANING, BITUMINOUS PAVEMENT
62,031	SY	U.S. ROUTE 7
2817	SY	U.S ROUTE 7 (NON-FEDERAL PARTICIPATING)
2256	SY	U.S. ROUTE 4
2799	SY	SIDEROADS
2844	SY	DRIVEWAYS
54	SY	ROUNDING
72,800	SY	TOTAL
		SUPERPAVE BITUMINOUS CONCRETE PAVEMENT (PG 70-28)
1805	TON	LEVELING COURSE (TYPE IVS)
79	TON	LEVELING COURSE (TYPE IVS) (NON-FEDERAL PARTICIPATING)
5418	TON	WEARING COURSE (TYPE IVS)
237	TON	WEARING COURSE (TYPE IVS) (NON-FEDERAL PARTICIPATING)
236	TON	SIDE ROADS
240	TON	DRIVEWAYS
35	TON	ROUNDING
8050	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #1

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(I)S

FILE NAME: p06d050.dgn
PROJECT LEADER: DEG
DESIGNED BY: MJL
IPARM FILE: p06d050qsl.i

PLOT DATE: 03-AUG-2012 12:2
DRAWN BY: CAK
CHECKED BY: DWE
SHEET 6 OF 76