QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

RAILROAD	NON PARTICIPATING	FULL C.E.	ROADWAY	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	488	-	15,712	16,200	LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	125
	-	-	25,900	25,900	LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412	127
	-	-	1850	1850	LF	DURABLE 8 INCH YELLOW LINE, THERMOPLASTIC	646.452	55
	65	-	760	825	LF	DURABLE 24 INCH STOP BAR, TYPE I TAPE	646.481	15
	-	-	190	190	EA	DURABLE LETTER OR SYMBOL, TYPE I TAPE	646.491	3
	65	-	1225	1290	LF	DURABLE CROSSWALK MARKING, THERMOPLASTIC	646.502	27
	-	-	4	4	EA	DURABLE RAILROAD CROSSING SYMBOL, TYPE I TAPE	646.511	-
	976	-	31,424	32,400	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST.
	-	-	51,800	51,800	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST.
	130	-	1520	1650	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST.
	-	-	308	308	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	EST.
	130	-	2450	2580	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	EST.
	-	-	8	8	EA	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712	-
	-	-	1250	1250	EA	LINE STRIPING TARGETS	646.76	EST.
	-	-	50	50	LB	SEED	651.15	EST.
	-	-	400	400	LB	FERTILIZER	651.18	EST.
	-	-	2	2	TON	AGRICULTURAL LIMESTONE	651.20	EST.
	-	-	2	2	TON	HAY MULCH	651.25	EST.
	-	-	50	50	CY	TOPSOIL	651.35	EST.
	-	-	1047	1047	SF	TRAFFIC SIGNS, TYPE A	675.20	0.09
						BEGIN SIGN POST OPTION ITEMS		
	-	-	2375	2375	LF	FLANGED CHANNEL SIGN POSTS	675.301	65
	-	-	2375	2375	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	65
						END SIGN POST OPTION ITEMS		
	-	-	375	375	LF	FLANGED CHANNEL SIGN POSTS	675.301	11
	-	-	575	575	LB	TUBULAR STEEL SIGN POST	675.33	20
	-	-	4	4	EA	FOUNDATION FOR TUBULAR STEEL SIGN POST	675.43	-
	-	-	217	217	EA	REMOVING SIGNS	675.50	-
	-	-	31	31	EA	ERECTING SALVAGED SIGNS	675.60	-
	-	-	1	1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ ALLEN STREET)	900.620	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ CRESCENT STREET)	900.620	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ CURTIS AVENUE)	900.620	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ PARK STREET)	900.620	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ STRONGS AVENUE)	900.620	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ U.S. ROUTE 4)	900.620	-
	-	-	1	1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (U.S. ROUTE 7 @ WEST STREET)	900.620	-
40	-	-	-	40	HR	SPECIAL PROVISION (FLAGGERS, RAILROAD)	900.630	EST.
1	-	-	-	1	LS	SPECIAL PROVISION (PAVED RAIL-HIGHWAY CROSSING) (U.S.7-AARDOT 851-286U)	900.645	-

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

QUANTITY SHEET #2

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: DEG
DESIGNED BY: MJL
IPARM FILE: p06d050qs2.i

PLOT DATE: 03-AUG-2012 12:2
DRAWN BY: CAK
CHECKED BY: DWE
SHEET 7 OF 76