ITEM DETAIL SUMMARY SHEET #5

LOCATION			DRAINAGE			SIDEWALK					REMARKS
			604.412	604.415	604.418	203.15	301.28	616.28	618.10	618.30	
BEGIN STATION	END STATION	POS.	REHAB. DI, CB, MH CLASS I	REHAB. DI, CB, MH CLASS II	REHAB. DI, CB, MH CLASS III	COMMON EXCAV.	SUBBASE OF CRUSHED GRAVEL	CAST-IN-PLACE CONC. CURB, TYPE B	P.C.C. SIDEWALK, 5 INCH	DETECTABLE WARNING SURFACE	
RUTLAND CITY:			EA	EA	EA	CY	TON	LF	SY	SF	
U.S. ROUTE 7											
133+00.0		LT				2.1	2.2	14	6.7	10	CONSTRUCT SIDEWALK RAMP, TYPE I WITH DETECTABLE WARNING SURFACE
133+24.0		LT		1							
133+35.0		LT				2.1	2.2	14	6.7	10	CONSTRUCT SIDEWALK RAMP, TYPE I WITH DETECTABLE WARNING SURFACE
133+41.0		RT	1								
133+67.0		LT	1								
135+18.0		LT		1							
135+18.0		RT	1								
139+65.0		LT	1								
139+65.0		RT	1								
146+56.0		LT	1								
146+56.0		RT	1								
U.S. ROUTE 4											
2+33.0		LT	1								
4+11.0		LT	1								
SUBTOTAL THIS SHEET			9	2	-	4.2	4.4	28	13.4	20	
SUBTOTAL SHEET 8			23	4	-	21.0	22.0	140	67.0	100	
SUBTOTAL SHEET 9			18	-	1	42.4	46.4	224	138.4	180	
SUBTOTAL SHEET 10			18	3	-	38.0	40.8	224	122.8	160	
SUBTOTAL SHEET 11			21	5	1	17.9	19.0	112	57.5	80	
ROUNDING			-	-	-	1.5	2.4	22	5.9	10	
TOTAL			89	14	2	125.0	135.0	750	405.0	550	

ITEM DETAIL SUMMARY SHEET #5

PROJECT NAME: RUILAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: DEG
DESIGNED BY: MJL
IPARM FILE: p06d050ids5.i

PLOT DATE: 03-AUG-2012 12:2
DRAWN BY: CAK
CHECKED BY: DWE
SHEET 12 OF 76