STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 3

| MILEMARKER, STATION, OR SIGN NUMBER | SIGN LEGEND | SIGN DIMENSIONS EA | WIDTH (in) | HEIGHT (in) | NEW & SALVAGED SIGNS "A" | "B" | SALV SIGN | SALV TIS | EXIST POST RETAIN | EXIST POST SALVAGE | NEW SIGN POSTS NO. OF POSTS | FLANGED CHANNEL lb/ft 1.12 | 2.0 | 3.0 | SQUARE STEEL (in) lb/ft 1.75 1.88 | 2.0 2.16 | 2.5 3.35 | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3 | 4.0 1.7 | 4.0 MOD 1.7 | TUBULAR STEEL Ø (in) FOUND-ATION | lb/ft 3.0 7.6 | 3.5 9.0 | 4.0 10.8 | 5.0 14.6 | W-SHAPE STEEL FTG. SIZE 24" | 30" | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL DETAIL ON DWG. NUMBER | STD. SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | | OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | | | |
| U.S. ROUTE 7: 6+97.0, LT | S MAIN ST / MARBLE AVE | | | | | | 1 / 1 | | | | 1 | | | X | | X | | X | | | | | | | | | | | | | | | SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. | - / - | - / - |
| | STOP 0070 1119 0014 | 1 / 1 | 30 / 6 | 30 / 10 | 6.25 / 0.42 | | | | | | | | | | | | | | | | | | | | | | | | | | | BACK TO BACK<br>SIGN ID CODE RI-1<br>SIGN ID CODE VD-700 | | E-143<br>E-138 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 7+32.0, LT | KEEP LEFT RIGHT | 1 | 12 | 18 | 1.50 | | | | | | 1 | | X | | X | | | X | | | | | | | | | | | | | | | SIGN ID CODE R9-7 | | E-143B |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8+05.0, LT | STOP HERE ON RED | 1 | 24 | 36 | 6.00 | | | | | | 1 | | | | | | | | | | | | 1 | 100 | | | | | | | | SIGN ID CODE RIO-6 | | E-140 |
| | END | 1 | 24 | 12 | 2.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID ~~CODE M4-6~~ | | E-140 |
| | CENTER LANE ONLY | 1 | 24 | 36 | 6.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 8+10.0, RT | BEGIN | 1 | 24 | 12 | 2.00 | | | | | | 1 | | | X | | X | | X | | | | | | | | | | | | | | | SIGN ID CODE M4-11 | | E-140 |
| | CENTER LANE ONLY | 1 | 24 | 36 | 6.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE R3-9B | | E-140 |
| 10+18.0, LT | DANA AVE / S MAIN ST | | | | | | 1 / 1 | | | | 1 | | | X | | X | | X | | | | | | | | | | | | | | | SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST. | - / - | - / - |
| | ONE WAY / ONE WAY | 1 / 1 | 36 / 36 | 12 / 12 | 3.00 / 3.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | BACK TO BACK<br>SIGN ID CODE R6-1L<br>SIGN ID CODE R6-1R | | E-142<br>E-142 |
| | DO NOT ENTER | 1 | 30 | 30 | 6.25 | | | | | | | | | | | | | | | | | | | | | | | | | | | SIGN ID CODE R5-1 | | E-143 |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| 10+40.0, LT | KEEP LEFT RIGHT | 1 | 12 | 18 | 1.50 | | | | | | 1 | | X | | X | | | X | | | | | | | | | | | | | | | SIGN ID CODE R9-7 | | E-143B |
| | | | | | | | | | | | | LF | LF 28 | LF 42 | LF 28 | LF 42 | LF | | EA. | LB | LB | LB | | LB 100 | LB | LB | LB | | | | | | | | |
| **TOTALS** | | SF 43.92 | SF | EA. 4 | SF | | | | | | | LF 70 | | | LF 70 | | | | | LB | | | EA. 1 | LB 100 | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

**TRAFFIC SIGN SUMMARY SHEET #3**

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(I)S

FILE NAME: p05b044.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06d050ss03.i
PLOT DATE: 03-AUG-2012 12
DRAWN BY: K.C.F.
CHECKED BY: D.W.E.
SHEET 47 OF 76