STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.16	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
U.S. ROUTE 7: 20+62.0, RT	USE PED SIGNAL / KEEP LEFT RIGHT	1 1	12 12	18 18	1.50 1.50						1		X		X			X																BACK-TO-BACK SIGN ID CODE R9-5 SIGN ID CODE R9-7		E-143B E-143B
20+65.0, LT	USE PED SIGNAL / KEEP LEFT RIGHT	1 1	12 12	18 18	1.50 1.50						1		X		X			X																BACK-TO-BACK SIGN ID CODE R9-5 SIGN ID CODE R9-7		E-143B E-143B
20+75.0, LT	KEEP LEFT RIGHT / USE PED SIGNAL	1 1	12 12	18 18	1.50 1.50						1		X		X			X																BACK-TO-BACK SIGN ID CODE R9-7 SIGN ID CODE R9-5		E-143B E-143B
20+75.0, RT	LEGAL LOAD LIMIT 18,000 POUNDS	1	24	30	5.00						1			X		X		X																SIGN ID CODE VR-017		E-141
21+33.0, RT	KEEP LEFT RIGHT / USE PED SIGNAL	1 1	12 12	18 18	1.50 1.50						1		X		X			X																BACK-TO-BACK SIGN ID CODE R9-7 SIGN ID CODE R9-5		E-143B E-143B
21+45.0, RT	S MAIN ST / ALLEN ST						1 1				1			X		X		X																SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	0070 1119 0040	1	6	10	0.42																													SIGN ID CODE VD-700		E-138
21+75.0, RT		1	36	36	9.00						2			X																					73	
22+70.0, RT	ONLY	1	48	30	10.00						2			X																				SIGN ID CODE VR-935 SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS		E-145B
23+00.0, RT	SPEED LIMIT 35	1	24	30	5.00						1			X		X		X																SIGN ID CODE R2-1		E-142
												LF	LF 56	LF 42 (56)	LF 56	LF 42	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS			SF 41.42			SF	EA. 2	SF				LF 98 (56)			LF 98					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #7

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06d050ss07.i

PLOT DATE: 03-AUG-2012 12
DRAWN BY: K.C.F.
CHECKED BY: D.W.E.
SHEET 51 OF 76