STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
U.S. ROUTE 7: 69+95.0, LT	ONLY ONLY	1	60	30	12.50						2			X																				SIGN ID CODE VR-941 SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS.		E-145A
72+16.0, RT	KEEP LEFT RIGHT	1	12	18	1.50						1		X		X			X															SIGN ID CODE R9-7		E-143B
72+49.0, RT	DO NOT ENTER	1 1	24 30	24 30	4.00 6.25						1			X		X		X															BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE R5-1		E-143 E-143
72+56.0, RT	NORTON ST N MAIN ST						1 1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
	STOP 0070 1119 0137	1 1	30 6	30 10	6.25 0.42						1			X		X		X															SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
	KEEP LEFT RIGHT	1	12	18	1.50						1		X		X			X															SIGN ID CODE R9-7		E-143B
73+05.0, LT	SPEED LIMIT 35	1	24	30	5.00						1			X		X		X															SIGN ID CODE R2-1		E-142
		1	24	24	4.00																											SIGN ID CODE R8-3A		E-143
	0070 1119 0130	1	6	10	0.42																											SIGN ID CODE VD-700		E-138
73+10.0, RT	ONLY ONLY	1	60	30	12.50						2			X																			SIGN ID CODE VR-941 SIGN SHALL BE MOUNTED ON TWO FLANGED CHANNEL SIGN POSTS		E-145A
												LF	LF 28	LF 42 (56)	LF 28	LF 42	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."																																			
	TOTALS				SF 54.34	SF	EA. 2	SF				LF 70 (56)			LF 70					LB			EA.	LB				EA.	EA.	LB						

TRAFFIC SIGN SUMMARY SHEET #11

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06d050ssll.i

PLOT DATE: 03-AUG-2012 12
DRAWN BY: K.C.F.
CHECKED BY: D.W.E.
SHEET 55 OF 76