STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 22

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 7: 103+12.0, RT	R	1	24	24	4.00						1			X		X		X															SIGN ID CODE R8-3A		E-143
103+38.0, RT	LEGAL LOAD LIMIT 18,000 POUNDS	1	24	30	5.00						1			X		X		X															SIGN ID CODE VR-017		E-141
103+45.0, RT	KEEP LEFT RIGHT	1	12	18	1.50						1		X		X			X															SIGN ID CODE R9-7		E-143B
103+87.0, RT	STOP 0070 1119 0196	1 1	30 6	30 10	6.25 0.42						1			X		X		X															BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
103+96.0, RT	NORTH ST N MAIN ST						1 1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- -	- -
103+97.0, RT	KEEP LEFT RIGHT	1	12	18	1.50						1		X		X			X															SIGN ID CODE R9-7		E-143B
104+70.0, LT	SPEED LIMIT 35	1	24	30	5.00						1			X		X		X															SIGN ID CODE R2-1		E-142
104+70.0, RT	SPEED LIMIT 35	1	24	30	5.00						1			X		X		X															SIGN ID CODE R2-1		E-142
106+17.0, LT	R	1	24	24	4.00						1			X		X		X															SIGN ID CODE R8-3A		E-143
												LF	LF 28	LF 98	LF 28	LF 98	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 32.67	SF	EA. 2	SF							LF 126			LF 126					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #22

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06d050ss22.i

PLOT DATE: 03-AUG-2012 12
DRAWN BY: K.C.F.
CHECKED BY: D.W.E.
SHEET 66 OF 76