STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.16	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUNDATION	lb/ft 3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
											OPTION ITEMS																									
U.S. ROUTE 7: 129+12.0, RT	SPEED LIMIT 35	1	24	30	5.00						1			X		X		X															SIGN ID CODE R2-1		E-142
132+74.0, LT	R	1	24	24	4.00						1			X		X		X															SIGN ID CODE R8-3A		E-143
132+95.0, LT	N MAIN ST / FIELD AVE						1 / 1				1			X		X		X															SALVAGED SIGN TO BE MOUNTED ON NEW POST. TOP MOUNTING BRACKET REQUIRED TO INSTALL SALVAGED SIGN ON NEW POST. COSTS ASSOCIATED WITH THIS BRACKET ARE INCIDENTAL TO THE SIGN POST.	- / -	- / -
133+00.0, LT	STOP + 0070 1119 0252	1 / 1	30 / 6	30 / 10	6.25 / 0.42						1			X		X		X															BACK TO BACK SIGN ID CODE RI-1 SIGN ID CODE VD-700		E-143 E-138
133+00.0, LT	KEEP LEFT RIGHT	1	12	18	1.50						1		X		X			X															SIGN ID CODE R9-7		E-143B
133+35.0, LT	KEEP LEFT RIGHT	1	12	18	1.50						1		X		X			X															SIGN ID CODE R9-7		E-143B
135+20.0, RT	END	1	24	12	2.00						1			X		X		X															SIGN ID CODE M4-6		E-140
		1	24	24	4.00																												SIGN ID CODE R5-6		E-143B
	ON TRAVELED LANES	1	24	18	3.00																													73	
135+23.0, LT	R	1	24	24	4.00						1			X		X		X															SIGN ID CODE R8-3A		E-143
												LF	LF 28	LF 84	LF 28	LF 84	LF		EA.	LB	LB	LB		LB	LB	LB	LB								
TOTALS		SF 31.67	SF	EA. 2	SF							LF 112			LF 112					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #25

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06d050ss25.i
PLOT DATE: 03-AUG-2012 12
DRAWN BY: K.C.F.
CHECKED BY: D.W.E.
SHEET 69 OF 76