STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 28

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																	REMARKS	SIGN DETAIL	
		EA	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POSTS	FLANGED CHANNEL lb/ft			SQUARE STEEL (in) lb/ft			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft			TUBULAR STEEL Ø (in) lb/ft					W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL ON DWG. NUMBER	STD. SHEET NUMBER
															1.75	2.0	2.5			3.0	4.0	4.0 MOD	FOUND-ATION	3.0	3.5	4.0	5.0	24"	30"					
												1.12	2.0	3.0	1.88	2.16	3.35			1.3	1.7	1.7		7.6	9.0	10.8	14.6							
												NON-OPTION ITEMS ( )																						
	SHEET 45 SUBTOTAL				40.00		-						-	70 (28)	-	70	-						-	-	-	-								
	SHEET 46 SUBTOTAL				34.50		1						56	28 (28)	56	14	14						-	-	-									
	SHEET 47 SUBTOTAL				43.92		4						28	42 (-)	28	42	-						1	100	-									
	SHEET 48 SUBTOTAL				41.67		-						28	56 (-)	28	56	-						-	-	-									
	SHEET 49 SUBTOTAL				46.42		1						14	70 (28)	14	70	-						-	-	-									
	SHEET 50 SUBTOTAL				49.25		-						-	84 (-)	-	56	28						-	-	-									
	SHEET 51 SUBTOTAL				41.42		2						56	42 (56)	56	42	-						-	-	-									
	SHEET 52 SUBTOTAL				48.84		1						28	56 (56)	28	56	-						-	-	-									
	SHEET 53 SUBTOTAL				46.25		-						42	42 (28)	42	14	28						-	-	-									
	SHEET 54 SUBTOTAL				51.57		-						-	28 (-)	-	-	28						1	-	165									
	SHEET 55 SUBTOTAL				54.34		2						28	42 (56)	28	42	-						-	-	-									
	SHEET 56 SUBTOTAL				53.95		-						28	14 (-)	28	14	-						2	290	-									
	SHEET 57 SUBTOTAL				36.67		1						56	42 (28)	56	28	14						-	-	-									
	SHEET 58 SUBTOTAL				30.30		1						14	70 (-)	14	56	14						-	-	-									
	SHEET 59 SUBTOTAL				30.84		1						56	56 (-)	56	56	-						-	-	-									
	SHEET 60 SUBTOTAL				25.84		3						42	70 (-)	42	70	-						-	-	-									
	SHEET 61 SUBTOTAL				29.92		-						42	56 (-)	42	42	14						-	-	-									
	SHEET 62 SUBTOTAL				25.59		3						14	70 (-)	14	56	14						-	-	-									
	SHEET 63 SUBTOTAL				31.00		-						14	42 (-)	14	42	-						-	-	-									
	SHEET 64 SUBTOTAL				36.67		1						-	84 (-)	-	84	-						-	-	-									
	SHEET 65 SUBTOTAL				28.67		2						28	70 (-)	28	56	14						-	-	-									
	SHEET 66 SUBTOTAL				32.67		2						28	98 (-)	28	98	-						-	-	-									
	SHEET 67 SUBTOTAL				37.84		-						-	98 (-)	-	84	14						-	-	-									
	SHEET 68 SUBTOTAL				34.09		1						28	84 (-)	28	70	14						-	-	-									
	SHEET 69 SUBTOTAL				31.67		2						28	84 (-)	28	84	-						-	-	-									
	SHEET 70 SUBTOTAL				35.09		-						-	84 (-)	-	70	14						-	-	-									
	SHEET 71 SUBTOTAL				47.92		3						-	70 (56)	-	70	-						-	-	-									
	SHEET SUBTOTAL				1046.91		31						658	1652 (364)	658	1442	210						4	390	165									
	ROUNDING				0.09		-						17	48 (11)	17	33	15						-	10	10									
												LF	LF 675	LF 1700 (375)	LF 675	LF 1475	LF 225		EA.	LB	LB	LB		LB 400	LB 175	LB	LB							
	TOTALS				SF 1047	SF	EA. 31	SF				LF 2375 (375)			LF 2375					LB			EA. 4	LB 575				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE ROADWAY, TRAFFIC AND SAFETY, AND PAVEMENT MANAGEMENT SECTION'S "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #28

PROJECT NAME: RUTLAND CITY
PROJECT NUMBER: NH 2605(1)S

FILE NAME: p06d050.dgn
PROJECT LEADER: D.E.G.
DESIGNED BY: M.J.L.
IPARM FILE: p06d050ss28.i

PLOT DATE: 03-AUG-2012 12
DRAWN BY: K.C.F.
CHECKED BY: D.W.E.
SHEET 72 OF 76