STATE OF VERMONT
AGENCY OF TRANSPORTATION

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
									ROADWAY	BRIDGE	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITY	UNIT	ITEMS
																				COLD PLANING, BITUMINOUS PAVEMENT
									15			15		EACH	THINNING AND TRIMMING FOR SIGNS	201.31	2	44451	SY	US 5
																		5434	SY	US 5 (SB)
									150			150		CY	COMMON EXCAVATION	203.15	22	4627	SY	US 5 TOWN HIGHWAYS
																		17824	SY	VT 142
									50			50		CY	SOLID ROCK EXCAVATION	203.16	6.7	199	SY	VT 142 TOWN HIGHWAYS
																		6583	SY	VT 30
									1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-	71	SY	VT 30 TOWN HIGHWAYS
																		555	SY	VT 119
									79800			79800		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	56			
																		79744	SY	SUBTOTAL
									250			250		TON	SUBBASE OF CRUSHED GRAVEL, FINE GRADED	301.28	26.8	56	SY	ROUNDING
																		79800	SY	TOTAL
									250			250		TON	AGGREGATE SHOULDERS, RAP	402.13	8			
									340			340		CWT	EMULSIFIED ASPHALT	404.65	9			
									1			1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
									9900			9900		TON	SUPERPAVE BITUMINOUS CONCRETE PAVEMENT	490.30	34			
									1			1		LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-			
										50		50		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3			
																				SUPERPAVE BITUMINOUS CONCRETE PAVEMENT
									35			35		LF	METAL HAND RAILING	525.15	2.1	4364	TON	US ROUTE 5, TYPE IVS, WEARING COURSE
									3			3		CY	CONCRETE, CLASS B	541.25	0.4	1456	TON	US ROUTE 5, TYPE IVS, LEVELING COURSE
										50		50		CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	-	1560	TON	VT ROUTE 142 TYPE IVS, WEARING COURSE
																		520	TON	VT ROUTE 142 TYPE IVS, LEVELING COURSE
									16			16		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40	-	61	TON	VT ROUTE 142, SHOULDER WIDENING, TYPE IIS
									64			64		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS I	604.412	-	576	TON	VT ROUTE 30 TYPE IVS, WEARING COURSE
									63			63		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS II	604.415	-	192	TON	VT ROUTE 30 TYPE IVS, LEVELING COURSE
									60			60		EACH	REHAB. DROP INLETS, CATCH BASINS, OR MANHOLES, CLASS III	604.418	-	49	TON	VT ROUTE 119 TYPE IVS, WEARING COURSE
									39			39		EACH	CHANGING ELEVATION OF SEWER MANHOLES	604.42	-	16	TON	VT ROUTE 119 TYPE IVS, LEVELING COURSE
									30			30		HR	POWER GRADER RENTAL	608.15	3	500	TON	SPOT LEVELING
									95			95		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.	405	TON	US ROUTE 5, TOWN HIGHWAYS, WEARING COURSE
									25			25		HR	POWER BROOM RENTAL, TYPE I	608.30	EST.	136	TON	US ROUTE 5, TOWN HIGHWAYS, LEVELING COURSE
									55			55		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.	17	TON	VT ROUTE 142, TOWN HIGHWAYS, WEARING COURSE
									95			95		HR	TRUCK RENTAL	608.37	EST.	6	TON	VT ROUTE 142, TOWN HIGHWAYS, LEVELING COURSE
									95			95		HR	LOADER RENTAL, TYPE I	608.40	EST.	6	TON	VT ROUTE 30, TOWN HIGHWAYS, WEARING COURSE
																		2	TON	VT ROUTE 30, TOWN HIGHWAYS, LEVELING COURSE
									100			100		CY	STONE FILL, TYPE I	613.10	EST.	9866	TON	SUBTOTAL
									230			230		LF	VERTICAL GRANITE CURB	616.21	4	34	TON	ROUNDING
									95			95		LF	PRECAST REINFORCED CONCRETE CURB, TYPE B	616.26	4	9900	TON	TOTAL
									65			65		LF	REMOVING AND RESETTING CURB	616.40	3			
									40			40		LF	REMOVAL OF EXISTING CURB	616.41	3			
									470			470		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10	22.2			
									830			830		SF	DETECTABLE WARNING SURFACE	618.30	10			
									164			164		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-			
									4000			4000		HR	UNIFORMED TRAFFIC OFFICERS	630.10	-			

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: STP 2623(11)

FILE NAME: /pave/06d214/pd214
PROJECT LEADER: PTS
DESIGNED BY: NLL
IPARM FILE NAME: 06D214_18

PLOT DATE: 3/19/2010
DRAWN BY: WWG
CHECKED BY: PTS/NLL
SHEET 18 OF 163

MODEL: Default
CLD 08-0324 z06D0214.dgn