STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75	SQUARE STEEL (in) lb/ft 2.0	SQUARE STEEL (in) lb/ft 2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0	TUBULAR STEEL Ø (in) lb/ft 3.5	TUBULAR STEEL Ø (in) lb/ft 4.0	TUBULAR STEEL Ø (in) lb/ft 5.0	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																								
US RTE 5																																				
STATION 14+28.32, LT US RTE 5	VR-921R LANE CONTROL SIGN	1	30	30	6.25						1			X																			INSTALL A NEW SIGN ON NEW POST		STD. E-145A
STATION 14+28.32, LT US RTE 5	BUS AND POLICE ZONE						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH THE PREVIOUS SIGN)		
STATION 15+59.95, LT US RTE 5	VR-921R LANE CONTROL SIGN	1	30	30	6.25						1			~~X~~																			INSTALL A NEW SIGN ON A NEW POST		STD. E-145A
STATION 16+47.13, RT US RTE 5	VR-921L LANE CONTROL SIGN	1	30	30	6.25						~~1~~			~~X~~																			INSTALL A NEW SIGN ON A NEW POST		STD. E-145A
16+69.62 STATION ~~16+81.12, LT~~ US RTE 5	M3-3, SOUTH	1	24	12	2.00						~~2~~						~~X~~	~~2~~	~~2~~														INSTALL A NEW SIGN ON A NEW POST		
16+69.62 STATION ~~16+81.12, LT~~ US RTE 5	M1-4, US ROUTE SIGN	1	24	24	4.00																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
16+69.62 STATION ~~16+81.12, LT~~ US RTE 5	M4-5, TO	1	24	12	2.00																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		STD. E-136B
16+69.62 STATION ~~16+81.12, LT~~ US RTE 5	VERMONT 119	1	30	24	5.00																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		STD. E-136B
16+69.62 STATION ~~16+81.12, LT~~ US RTE 5	VERMONT 142	1	30	24	5.00																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 17+24.07, LT US RTE 5	NO PARKING HERE TO CORNER	1	12	18	1.50						1		X																				INSTALL A NEW SIGN ON A NEW POST		
STATION 17+80.60, RT US RTE 5	WHEN CLEAR STROBE IS FLASHING R.R. GATES ARE DOWN AT VT 119	1	36	24	6.00																												INSTALL A NEW SIGN ON PEDESTAL POST (SEE TRAFFIC SIGNAL SHEET 4 FOR LOCATION)	SHEET 153	
STATION 17+98.37, RT US RTE 5	NO PARKING ⟷	1	12	18	1.50						1		X																				INSTALL A NEW SIGN ON A NEW POST		
STATION 18+46.14, LT US RTE 5	NO RIGHT TURN ON RED	1	24	30	5.00						1			X																			INSTALL A NEW SIGN ON A NEW POST		
STATION 18+94.78, LT US RTE 5	BUS AND POLICE ZONE	1	24	30	5.00				1																								INSTALL A NEW SIGN ON EXISTING POST		
STATION 19+18.40, RT US RTE 5	NORTH	1	24	12	2.00																												INSTALL A NEW SIGN ON LIGHT POLE		
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
													23.26	50.74		74.00	37.00		2																
	TOTALS	SF 57.75	SF	EA. 1	SF							FT 74.00				FT 37.00				LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: STP 2000(24)

FILE NAME:
PROJECT LEADER: KEN UPMAL
DESIGNED BY: A.ACHARYA
TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 3/19/2010
DRAWN BY: A.ACHARYA
CHECKED BY: V. KACOYANNAKIS
SHEET 143 OF 163