STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.0 (2.42)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SIGN FRAME REQUIRED	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																								
VT RTE 9																																			
STATION 71+16.36, RT VT RTE 9	NO RIGHT TURN ON RED — R10-1IB, NO TURN ON RED	1	24	30	5.00						1			X																			INSTALL A NEW SIGN ON NEW POST		
STATION 71+31.06, RT VT RTE 9	HIGH ST — D1-1, GUIDE SIGN HIGH ST						1				1			X																			INSTALL SALVAGED SIGN ON NEW POST		
STATION 71+31.06, RT VT RTE 9	MAIN ST — D1-1, GUIDE SIGN MAIN ST						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 71+31.06, RT VT RTE 9	ALL DAY PARKING — PARKING						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
GROVE STREET																																			
STATION 80+86.65, RT GROVE STREET	STOP — R1-1, STOP	1	30	30	6.25						1 ~~2~~			X																			INSTALL A NEW SIGN ON A NEW POST		
STATION 80+86.65, RT GROVE STREET	R3-2, LEFT TURN PROHIBITED	1	30	30	6.25																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 80+96.40, RT GROVE STREET	GROVE ST — D1-1, GUIDE SIGN GROVE ST	SIGN WAS NOT PRESENT					~~1~~				1			X																			INSTALL SALVAGED SIGN ON NEW POST		
STATION 80+96.40, RT GROVE STREET	MAIN ST — D1-1, GUIDE SIGN MAIN ST						~~1~~																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 80+96.40, RT GROVE STREET	NO PARKING BETWEEN SIGNS — NO PARKING						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 80+96.40, RT GROVE STREET	ALL DAY PARKING — PARKING						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
HARRIS PLACE																																			
STATION 128+14, RT HARRIS PLACE	MAIN ST — D1-1, GUIDE SIGN MAIN ST						1				2			X																			INSTALL SALVAGED SIGN ON NEW POSTS		
STATION 128+14, RT HARRIS PLACE	HARRIS PL — D1-1, GUIDE SIGN HARRIS PL						1																										INSTALL SALVAGED SIGN ON NEW POSTS (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 128+14, RT HARRIS PLACE	STOP — R1-1, STOP	1	30	30	6.25																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
												FT	FT	FT 94.00	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB							
TOTALS					SF 23.75	SF	EA. ~~9~~ 7	SF				FT 94.00			FT					LB			EA.	LB				EA.	EA.	LB				

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: STP 2000(24)

FILE NAME:
PROJECT LEADER: KEN UPMAL
DESIGNED BY: A.ACHARYA
TRAFFIC SIGN SUMMARY SHEET 7

PLOT DATE: 3/19/2010
DRAWN BY: A.ACHARYA
CHECKED BY: V. KACOYANNAKIS
SHEET 147 OF 163