STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 2

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
												OPTION ITEMS																									
US RTE 5																																			
STATION 10+52.34, RT US RTE 5	STOP RI-1, STOP	1	30	30	6.25																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH EXISTING SIGNS)		
STATION 10+52.34, RT US RTE 5	0050 1302 0216 MILE MARKER	1	6	10	0.42																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT BACK TO BACK WITH PREVIOUS SIGNS)		STD. E-138
STATION 10+65.93, RT US RTE 5	ONLY VR-92IL LANE CONTROL SIGN	1	30	30	6.25						2			X																			INSTALL A NEW SIGN ON A NEW POST		STD. E-145A
STATION 10+65.93, RT US RTE 5	DO NOT BLOCK INTERSECTION R10-7, DO NOT BLOCK INTERSECTION	1	24	30	6.00																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH EXISTING SIGNS)		
STATION 10+67.12, LT US RTE 5	P ARKING PARKING AREA SIGN		MISSING				~~1~~				1			X		POST IN, NO SIGN																INSTALL SALVAGED SIGN ON NEW POST		
STATION 10+94.98, RT US RTE 5	WHEN CLEAR STROBE IS FLASHING R.R. GATES ARE DOWN AT VT 119 RAILROAD PRE-EMPTION	1	36	24	6.00																												INSTALL A NEW SIGN ON PEDESTAL POST (SEE TRAFFIC SIGNAL SHEET 2 FOR LOCATION)	SHEET 151	
STATION 11+41.03, LT US RTE 5	NO RIGHT TURN ON RED R10-11B, NO TURN ON RED	1	24	30	5.00						1			X																			INSTALL A NEW SIGN ON NEW POST		
STATION 11+57.77, RT US RTE 5	NORTH M3-1, NORTH	1	24	12	2.00																												INSTALL A NEW SIGN ON LIGHT POLE		
STATION 11+57.77, RT US RTE 5	5 M1-4, US ROUTE SIGN	1	24	24	4.00																												INSTALL A NEW SIGN ON LIGHT POLE (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 12+27.34, RT US RTE 5	ONLY VR-92IL LANE CONTROL SIGN	1	30	30	6.25																												INSTALL A NEW SIGN ON LIGHT POLE		STD. E-145A
STATION 13+13.15, RT US RTE 5	ONLY VR-92IL LANE CONTROL SIGN	1	30	30	6.25						1			X																			INSTALL A NEW SIGN ON NEW POST		STD. E-145A
STATION 13+41.29, LT US RTE 5	ELLIOT ST DI-1, GUIDE SIGN ELLIOT ST						1				1			X																			INSTALL SALVAGED SIGN ON NEW POST		
STATION 13+41.29, LT US RTE 5	MAIN ST DI-1, GUIDE SIGN MAIN ST						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 13+53.68, RT US RTE 5	WHEN CLEAR STROBE IS FLASHING R.R. GATES ARE DOWN AT VT 119 RAILROAD PRE-EMPTION	1	36	24	6.00																												INSTALL A NEW SIGN ON PEDESTAL POST (SEE TRAFFIC SIGNAL SHEET 3 FOR LOCATION)	SHEET 152	
MOVED STATION ~~14+11.34, LT~~ US RTE 5	NO RIGHT TURN ON RED R10-11B, NO TURN ON RED	1	24	30	5.00						1			X																			INSTALL A NEW SIGN ON NEW POST		
												FT	FT	FT 91.00	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 59.42	SF	EA. ~~3~~ 2	SF				FT 91.00			FT					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

TO BE INSTALLED BY MOULLISON

TO BE INSTALLED BY MOULLISON

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: STP 2000(24)

FILE NAME:
PROJECT LEADER: KEN UPMAL
DESIGNED BY: A.ACHARYA
TRAFFIC SIGN SUMMARY SHEET 2

PLOT DATE: 4/8/2010
DRAWN BY: A.ACHARYA
CHECKED BY: V. KACOYANNAKIS
SHEET 142 OF 163