STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 4

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) 1.75 lb/ft 1.88	SQUARE STEEL (in) 2.0 lb/ft 2.42	SQUARE STEEL (in) 2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) 3.0 lb/ft 1.3	TUBULAR ALUMINUM Ø (in) 4.0 lb/ft 1.7	TUBULAR ALUMINUM Ø (in) 4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) 3.0 lb/ft 7.6	TUBULAR STEEL Ø (in) 3.5 lb/ft 9.0	TUBULAR STEEL Ø (in) 4.0 lb/ft 10.8	TUBULAR STEEL Ø (in) 5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
											OPTION ITEMS																									
US RTE 5																																			
STATION 19+18.40, RT US RTE 5	MI-4, US ROUTE SIGN	1	24	24	4.00																												INSTALL A NEW SIGN ON LIGHT POLE (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 19+18.40, RT US RTE 5	M3-2, EAST	1	24	12	2.00																												INSTALL A NEW SIGN ON LIGHT POLE (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 19+18.40, RT US RTE 5	VERMONT 9	1	24	24	4.00																												INSTALL A NEW SIGN ON LIGHT POLE (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 20+31.21, LT US RTE 5	VR-92IR LANE CONTROL SIGN	1	30	30	6.25						~~2~~			X																			INSTALL A NEW SIGN ON A NEW POST		STD. E-145A
STATION 20+31.21, LT US RTE 5	TOW-AWAY ZONE	1	12	6	0.50																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 20+31.21, LT US RTE 5	R7-2a NO PARKING	1	12	18	1.50																												INSTALL A NEW SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 20+31.21, LT US RTE 5	NO IDLING						1																										INSTALL SALVAGED SIGN ON NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 20+49.14, RT US RTE 5	W11-2, PEDESTRIAN AHEAD	1	30	30	6.25						1			X																			INSTALL A NEW SIGN ON A NEW POST TYPE IX FLUORESCENT YELLOW GREEN BACKGROUND RETROREFLECTIVE SHEETING		
STATION 20+49.14, RT US RTE 5	W16-2 200 FT	1	24	18	3.00																												INSTALL A NEW SIGN ON A NEW POST TYPE IX FLUORESCENT YELLOW GREEN BACKGROUND RETROREFLECTIVE SHEETING (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 21+02.58, RT US RTE 5	NO PARKING BUS STOP	1	12	18	1.50						1			X																			INSTALL A NEW SIGN ON A NEW POST		
STATION 21+02.58, RT US RTE 5	THE BRATTLEBORO BEELINE						1																										INSTALL SALVAGED SIGN ON A NEW POST (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 22+31.34, RT US RTE 5	W11-2, PEDESTRIAN AHEAD	1	30	30	6.25						1																						INSTALL A NEW SIGN ON EXISTING POST TYPE IX FLUORESCENT YELLOW GREEN BACKGROUND RETROREFLECTIVE SHEETING		
STATION 22+31.34, RT US RTE 5	W16-7p ARROW	1	24	12	2.00																												INSTALL A NEW SIGN ON EXISTING POST TYPE IX FLUORESCENT YELLOW GREEN BACKGROUND RETROREFLECTIVE SHEETING (SUB-MOUNT WITH PREVIOUS SIGN)		
STATION 23+22.56, RT US RTE 5	VR-92IL LANE CONTROL SIGN	1	30	30	6.25																												INSTALL A NEW SIGN ON LIGHT POLE		STD. E-145A
STATION 22+60.30, LT US RTE 5	W11-2, PEDESTRIAN AHEAD	1	30	30	6.25						1			X																			INSTALL A NEW SIGN ON A NEW POST TYPE IX FLUORESCENT YELLOW GREEN BACKGROUND RETROREFLECTIVE SHEETING		
												FT	FT	FT 75.25	FT	FT	FT		EA 4	LB	LB	LB		LB	LB	LB	LB								
TOTALS					SF 49.75	SF	EA. ~~2~~ 1	SF				FT 75.25			FT					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE".

PROJECT NAME: BRATTLEBORO
PROJECT NUMBER: STP 2000(24)

FILE NAME:
PROJECT LEADER: KEN UPMAL
DESIGNED BY: A.ACHARYA
TRAFFIC SIGN SUMMARY SHEET 4

PLOT DATE: 3/19/2010
DRAWN BY: A.ACHARYA
CHECKED BY: V. KACOYANNAKIS
SHEET 144 OF 163